

July 27, 2009

Mr. Jaime Rabins
Illinois Environmental Protection Agency
Division of Water Pollution Control
1021 North Grand Avenue East
Springfield, Illinois 62702

RE: Application for Permit or Construction Approval
Metal Cleaning Basin Liner Replacement
Midwest Generation Powerton Power Station
13082 East Manito Road, Pekin, IL
NPDES Permit No. IL.0002232

Dear Mr. Rabins,

Midwest Generation, LLC (MWG) is requesting a construction permit for liner replacement in the Metal Cleaning Basin at the Powerton Power Station. This activity is part of MWG's routine maintenance program for the facility; no significant modifications will be made to the basin's operation or treatment process. Please find enclosed a copy of the Application for Permit or Construction Approval WPC-PS-1 and supporting documents.

The following information is attached:

- A site location map is included in the "Figure" tab;
- A plan view of existing conditions, liner replacement plan, cross section and details drawings are included in the "Sheets" tab,
- Form WPC-PS-1 "Application for Permit or Construction Approval", and Schedules G "Sludge Disposal & Utilization", J "Industrial Treatment Works Construction or Pretreatment Works", and N "Waste Characteristics" are provided in Appendix A;
- Representative photographs of the Metal Cleaning Basin are provided in Appendix B; and
- Specification Section 02600 for installation of high-density polyethylene (HDPE) geomembrane liner is provided in Appendix C.

Midwest Generation EME, LLC One Financial Place 440 South LaSalle Street Suite 3500 Chicago, IL 60605 Tel: 312 583 6062

Tel: 312 583 6002 Fax: 312 788 552n Fmail mracc@ms gan com





Mr. Jaime Rabins, Div. of Water Pollution Control, IEPA July 27, 2009 Page 2

FACILITY DESCRIPTION

The Metal Cleaning Basin is for settling of solid/sludge waste from cleaning/wash water associated with boiler maintenance at the Powerton Generating Station. The basin is operational when maintenance activities are conducted, which is generally between March and June each year. The total depth of the basin is 12 feet with a capacity of approximately 5.4 million gallons. Typically, the basin freeboard ranges between 3 and 6 feet during operation. Currently, the basin is lined with Hypalon® geomembrane on the side slopes, and a 12-inch thick layer of Poz-o-pac¹ at the base (Sheet C010) and 5 feet up the side slopes. Photographs of the current condition of the basin are provided in Appendix B.

PROJECT DESCRIPTION

Liner replacement activities for the Metal Cleaning Basin are anticipated to occur in October/November 2009, following scheduled dredging activities (dewatering followed by dry excavation):-This schedule may change based upon plant operation needs. Liner replacement activities will include:

- Subgrade preparation for HDPE geomembrane liner (Sheet C020), including removal of the existing Poz-o-Pac liner along the side slopes of the basin (i.e., 12 inches of Poz-o-pac to remain at the base), and removal of the concrete aprons for the inlet pipes;
- Deployment and seaming of the HDPE geomembrane replacement liner. The permeability² of geomembrane is typically between 2x10⁻¹³ and 4x10⁻¹³ centimeters per second; and
- Placement of cushion and warning layers over the replacement liner.

The warning layer will consist of dense-graded aggregate, grade no. CA6 conforming to Section 1004.01, Coarse Aggregate of State of Illinois, Department of Transportation (IDOT), Standard Specifications for Road and Bridge Construction, or other easily-identifiable material.

The cushion layer will consist of sand, or limestone screenings grade no. FA 1, FA 2, FA3 or FA5 conforming to Section 1003.01 Fine Aggregate of IDOT Standard Specifications for Road and Bridge

Midwest Generation EME, LLC One Emoneial Place 440 South EuSoffe Street Suite 3500 Chicago, H. 60005 Tcl. 342 583 6062 fax 342 588 5520 Final Induced imagences

A stabilized subgrade that is comprised of lime, fly ash and aggregate. Compressive strength could be between 500 to 1,000 psi.

² Koerner, Robert M., and David E. Daniel, Final Covers for Solid Waste Landfills and Abandoned Dumps, ASCE Press, 1997

Maria L. Race Environmental Program Manager

Mr. Jaime Rabins, Div. of Water Pollution Control, IEPA July 27, 2009
Page 3

Construction.

The proposed HDPE geomembrane replacement liner, associated anchor trenches, and cushion and warning layers are shown on Sheet C030. Cross sections and details associated with the liner and cushion/warning layers are shown on Sheets C031 and C032.

If you have any questions or require additional information as you review this application, please call me at 312-583-6062.

Sincerely,

Maria Race

Environmental Program Manager

Attachments: Figure 1 - Site Location Map

Appendix A - WPC-PS-1 and Schedules G, J and N

Appendix B - Site Photographs

- 2. Roe-

Appendix C - Specification Section 02600, HDPE Geomembrane

Sheet C010 – Existing Conditions

Sheet C020 - Liner Subgrade Preparation

Sheet C030 – Warning Layer Plan Sheet C031 – Details and Sections Sheet C032 – Details and Sections


cc: Mr. Mark Kelly, MWG-Powerton

[1965 Metal Cleaning Basin letter DRAFT 090715]

Midwest Generation EME, LLC One Financial Place 440 South LaSaffe Street Suite 5500 Chicago, IL 60603 Tel: 312 583 6062

Fax: 312 788 3526 Email mace@mwgen.com

FIGURE



19.3

1

200

No.

ABOTE A DELEVANO A MEL PARENTA SERVICIO DE LA MANTE DEL LA MANTE DE LA MANTE DEL LA MANTE DE LA MANTE DEL LA MANTE DE LA MANTE

APPENDIX A

APPLICATION FOR PERMIT OR CONSTRUCTION APPROVAL (WPC-PS-1 AND SCHEDULES G, J AND N)



Illinois Environmental Protection Agency Permit Section, Division of Water Pollution Control P.O. Box 19276 Springfield, Illinois 62794-9276

For 1	EPA Us	ie:	

Application for Permit or Construction Approval WPC-PS-1

Brief Description of Project: Maintenance on Metal Cleaning Basin includes replacement of the pond liner. There will be no significant to current operation of the pond. Documents Being Submitted: If the Project involves any of the items listed below, submit the corresponding and check the appropriate boxes. Private Sewer Connection/Extension Sewer Extension Construct Only Sewer Extension Construct Only Sewage Treatment Works Industrial Treatment/Pretreatment Excess Flow Treatment Excess Flow Treatment Excess Flow Treatment Fast Track Service Connection FTP Trust Disclosure Plans: Title Metal Cleaning Basin Liner Replacement, Midwest Generation, Powerton Power Station, Pekin, IL No. of Pages: Other Documents: Facility photos (see attached) (Please Specify) 1 Illinois Historic Preservation Agency approval letter: Yes \(\sqrt{No} \) \(\sqrt{V} \)	nt change
Maintenance on Metal Cleaning Basin includes replacement of the pond liner. There will be no significant to current operation of the pond. Documents Being Submitted: If the Project involves any of the items listed below, submit the corresponding and check the appropriate boxes. Schedule Private Sewer Connection/Extension Sewer Extension Construct Only CSeptic Tanks Sewage Treatment Works DIDITION Treatment/Pretreatment Excess Flow Treatment Lift Station/Force Main FIDITION Trust Disclosure Studge Disposal Plans: Title Metal Cleaning Basin Liner Replacement, Midwest Generation, Powerton Power Station, Pekin, IL No. of Pages: Specifications: Title Section 02600, High Density Polyethylene (HDPE) Geomembrane No. of Books/Pages: Other Documents: Facility photos (see attached) (Please Specify)	nt change
Documents Being Submitted: If the Project involves any of the items listed below, submit the corresponding and check the appropriate boxes. Schedule	nt change
and check the appropriate boxes. Schedule	
Private Sewer Connection/Extension Sewer Extension Construct Only Sewage Treatment Works Lift Station/Force Main Fast Track Service Connection Studge Disposal Plans: Title Metal Cleaning Basin Liner Replacement, Midwest Generation, Powerton Power Station, Pekin, IL Specifications: Title Section 02600, High Density Polyethylene (HDPE) Geomembrane No. of Books/Pages: Other Documents: Facility photos (see attached) (Please Specify)	ing schee
Seware Extension Construct Only Sewage Treatment Works D	Schedule
Sewage Treatment Works Excess Flow Treatment Froston Control Froston Control Trust Disclosure Studge Disposal Fittle Metal Cleaning Basin Liner Replacement, Midwest Generation, Powerton Power Station, Pekin, IL No. of Pages: Other Documents: Facility photos (see attached) (Please Specify)	_ H 🔲
Excess Flow Treatment Lift Station/Force Main Fast Track Service Connection Studge Disposal Plans: Title Metal Cleaning Basin Liner Replacement, Midwest Generation, Powerton Power Station, Pekin, IL No. of Pages: Specifications: Title Section 02600, High Density Polyethylene (HDPE) Geomembrane No. of Books/Pages: Other Documents: Facility photos (see attached) (Please Specify)	<u> </u>
Lift Station/Force Main	7 🔼
Fast Track Service Connection Sludge Disposal Plans: Title Metal Cleaning Basin Liner Replacement, Midwest Generation, Powerton Power Station, Pekin, IL No. of Pages: Specifications: Title Section 02600, High Density Polyethylene (HDPE) Geomembrane No. of Books/Pages: Other Documents: Facility photos (see attached) (Please Specify)	N
Plans: Title Metal Cleaning Basin Liner Replacement, Midwest Generation, Powerton Power Station, Pekin, IL No. of Pages: Specifications: Title Section 02600, High Density Polyethylene (HDPE) Geomembrane No. of Books/Pages: Other Documents: Facility photos (see attached) (Please Specify)	P
Plans: Title Metal Cleaning Basin Liner Replacement, Midwest Generation, Powerton Power Station, Pekin, IL No. of Pages: Specifications: Title Section 02600, High Density Polyethylene (HDPE) Geomembrane No. of Books/Pages: Other Documents: Facility photos (see attached) (Please Specify)	
Other Documents: Facility photos (see attached) (Please Specify)	4
Other Documents: Facility photos (see attached) (Please Specify)	
(Please Specify)	20
	2
1 Illinois Historic Presentation Agency approved letter: Ves DNo [7]	
Thiniois Thatoric Frescreation Agency approval letter. Tes [170 [2]	
Land Trust: Is the project identified in item number 1 herein, for which a permit is requested, to be construend which is the subject of a trust? Yes \sum No \subseteq	ucted on
If yes, Schedule T (Trust Disclosure) must be completed and item number 7.1.1 must be signed by a bend trustee or trust officer.	eficiary,
This is an Application for (Check Appropriate Line):	
A. Joint Construction and Operating Permit	
B. Authorization to Construct (See Instructions) NPDES Permit No. IL00 02232	
C. Construct Only Permit (Does Not Include Operations)	

Certifications and Approvar.		
6.1 Certificate by Design Engineer (I hereby certify that I am familiar with the indicated above, and that to the best of the The plans and specifications (specifications) as described above were preparations.	my knowledge and belief such informous other than Standard Specifications	ration, including the attached schedules nation is true, complete and accurate.
Engineer Name: Heather M. Simon		WILLING COMME
Registration Number: 062 - (3 digits) (Firm: Natural Resource Technology, Inc.		HEATHER M. SIMON GGZ.OSCHOOL WATERTOWN WI
Address: 23713 W. Paul Rd, Suite D		WATERTOWN IS
Describes		MALE MILLION
City: Pewaukee	State: WI Zip; 53072	Phone No:
Signature X	William .	Date: 7/27/25
I/We hereby certify that I/we have read a and am/are authorized to sign this applic Control Board. I/We hereby agree to comade part of this Permit. 7.1/1 Name of Applicant for Permit to Company of Applicant for Permit to Comp	cation in accordance with the Rules of the form with the Standard Conditions on truct: Midwest Generation EME.	and Regulations of the Illinois Pollution and with any other Special Conditions
Address: 13082 E Manito Road		//
City: Pekin	State: IL	_ '
Printed Name: Mike Hanrahan		Phone No:
Title:	HE SHIP THE	AS IN THE PERSON OF THE PERSON
Organization:		
	arram eve e la se de	the state of the s
7.1.2 Name of Applicant for Permit to O		
7.1.2 Name of Applicant for Permit to Or		
The state of the state of		

Signature X _

Title:

Printed Name: ___

Date:

Phone No: _

_	•X		Date:	
le:				
		(City Cleri	k, Village Clerk, Sanitary D	istrict Clerk, Etc.
	applications from non-governmental applicant rincipal executive officer of at least the level of			
C	Certificate By Intermediate Sewer Owner N	I/A		
I here	eby certify that (Please check one):			
	 The sewers to which this project will be trit wastewater that will be added by this project Act or Subtitle C. Chapter I, or 	ect without causing a	violation of the environme	ntal Protection
□ 2	The Illinois Pollution Control Board, in PCE variance from Subtitle C, Chapter I to allow	3	dated	granted a
Court	v Suntan Oumer		WAS TAKEN IN WAIT	
	ess:			
	iture X			
Printe	ed Name:		Phone No:	
7.4.1	Additional Certificate By Intermediate Sewer	Owner N/A		
l here	by certify that (Please check one):			
<u> </u>	 The sewers to which this project will be trib wastewater that will be added by this proje Act or Subtitle C. Chapter I, or 			
<u> </u>	The Illinois Pollution Control Board, in PCE variance from Subtitle C, Chapter I to allow	s construction facilities	_dated	granted a
Пз	Not applicable	v Construction (aciille	se met ere trie subject Of (II)	па аррисацон.
J.	and location of sewer system to which this p	roject will be tributar	y :	
	5			
Name	r System Owner:			
Name	E			

Printed	d Name:	Phone No:		
Title: _				_ = -5-(154
7.5 Ce	ertificate By Waste Treatment Works Owner N/	A		
I hereb	by certify that (Please check one):			
1 1.	The waste treatment plant to which this project wastewater that will be added by this project with Act or Subtitle C, Chapter I, or	rill be tributary h nout causing a vi	as adequate reserve olation of the Enviro	e capacity to treat the onmental Protection
□ 2.	The Illinois Pollution Control Board, in PCB Subtitle C, Chapter I to allow construction and op	peration of the fa	cilities that are the s	subject of this
□3.	Not applicable			
treated				
	of Waste Treatment Works: Treatment Works Owner:			
	ss:			
Signati	ure X		_ Date:	*
Printed	Name:	F	hone No:	
Title:				2

Please return completed form to the following address:

Illinois Environmental Protection Agency Permit Section, Division of Water Pollution Control P.O. Box 19276 Springfield, Illinois 62794-9276

This Agency is authorized to require this information under littinois Revised Statues, 1979, Chapter 111 1/2, Section 1039. Disclosure of this information is required under that Section. Failure to do so may prevent this form from being processed and could result in your application being denied. This form has been approved by the Forms Management Center.

IL 532-0010 WPC 150 This Agency is authorized to require this information under filinois Revised Statutes, 1979, Chapter 111 1/2, Section 1039. Disclosure of this information is required under that section. Failure to do so may prevent this form from being processed and could result in your application being denied.

For IEPA Use:	10
LOG#	
DATE RECEIVED:	

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL PERMIT SECTION Springfield, Illinois 62794-9276

SCHEDULE G SLUDGE DISPOSAL & UTILIZATION

1.	Nar	ne of F	Project Powerton Metal Cleaning Basin Liner Replacement
2.	Ger	neral in	nformation
	2.1	Soure	ce(s) Boiler wash water
	2.2	Produ	luction Volume per year 2,350 tons Dry Tons per year NA
	2.3	Sludg	ge to be disposed of is: Liquid NA Dry Tons NA
	2.4	Slude	ge is: Aerobically digested 🔲 , Anaerobically digested 🔲 , Heat Anaerobically digested 🔲 , Raw 🔲 , Chemically
			ilized, Composted, Wastewater Lagoon, WTP Lime, WTP Alum, WTP Iron, Other 🔀,
			ner, describe Coal Ash . Mixture . If mixture, describe
	2.5		e sludge defined as hazardous by State or Federal Law? YES NO 🔀 . If yes, basis.
	2.6	Is slu	udge to be stored on the STP site? YES NO X If yes, type of storage, lagoon , storage tank , capacity of storage, capacity of storage storage, capacity of storage storage, capacity of storage stora
	2.7	Sludg	ige Hauling
		2.7.1	Name(s), address(es) and Illinois Transporters I.D. Numbers
			Dave Clinard Trucking - DOT# 280869 Route 24 West; Mt. Sterling, IL 62353
		2.7.2	For industrial generators, has Illinois Generator ID Number and Authorization Number been issued? YES X NO
_			If no, contact the Division of Land Pollution Control.
			Illinois Generator ID Number ILD000665471
			Authorization Number 9290-99
2	Mai	hode d	of Sludge Disposal and/or Utilization
J.	IAIG	inous c	or ordege disposar and/or offinearion
	3.1	Land	Application (
		3.1.1	Indicate the number of dry tons of sludge per year to be disposed by each of the following methods:
			Agricultural land 🔲 , Commercial Fertilizer Production 🔲 , Dedicated Land Disposal 🔲 , Disturbed Land
			Reclamation 🗵 , Silviculture 🔲 , Horticultural Lands 🔲 , Public Distribution 🔲 , Other 🔲 ,
			If other, specify
		3.1.2	Sludge Disposal Site Location. Provide a map (USGS Quadrangle map or plat map) showing location.
			Name of USGS Quadrangle Map (7.5 or 15 minute) or plat map
		3.1.3	3 Provide soil survey map and soil description for disposal site. Identify name of soil survey and map sheet number each soil survey map provided.

3.1,	Is sludge to be stored at disposal s cubic feet.	ite? YES NO . If yes,	describe and state the storage volume
3.1.	Provide a copy of sludge user inform	mation sheet and completed. s	signed copies for any known users
3.1)	pollution, potable water supply wellh total acres available, soil characteri	ead protection and other buffer	n features to prevent ground and/or surface wate distances, calculations supporting storage capacity s, etc.
	Disposed at Coal Mine once a ye	ear at:	***
	Buckheart Mine		
	22116 E County 6 Hwy	PARA HISTORY	
	Canton, IL 61520	V	
3,1,7	Submit calculations of sludge applic	THE RESIDENCE OF STREET, AND THE PARTY OF THE PARTY OF THE PARTY.	organic loading and metal loading rate.
			organic loading the metal loading rate.
3.2 Land	ifilling on-site off-sit	e	
3.2.1		e Landfill 📗 Hazardous Was	ste Landfill Other
	If other, specify	<u> </u>	
3.2.2	Name and Location of Landfill(s)		
	to see the second		DESCRIPTION OF THE PROPERTY OF
3.2.3	IEPA Permit Number(s)	w i []ene	
	= 10/1 Htc.1=	(1521) - II-16 II.	
3.3 Incin			
	The state of the s		
3.3.1	Name and Location NA		
3.3.2	IEPA Permit Number(s)		
3.3.3	Ultimate Disposal of Incinerator res	due	
4. Sludge C	haracteristics		
Submit c	omolete analyses of sludge character	istics in make dry wt. basis u	nless otherwise indicated. The analyses shall be
performe	d unless the sludge is disposed of by	incineration or at an off-site la	ndfill. Analyses performed shall include but not be
imited to	parameters below:		
Paramet	er .	Parameter	
% TS % VS		Sulfur Aluminum (total)	
COD mg/		Arsenic (total)	
pН		Barium (total)	
	The server and the se	Cadmium (total)	
	eq of CaCO3 at pH	Cobalt (total)	
	meq of CaCO3 at pH	Chromium, hex (total)	
	rease mg/l	Chromium (total)	
Phenois :	ng/i	Copper (total)	
Cyanide Sulfate (to	Itali mall	Iron (total)	
Sulfide (to		Mercury (total) Manganese (total)	
Sodium	real tight	Molybdenum (total)	
EC mmh	os/cm	Nickel (total)	
TOC	•	Lead (total)	

Store Fourthead

Ammonia mg/l
Total Kjeldahl Nitrogen mg/l
Phosphorus
Potassium
% Volatile Acids, if anaerobically digested

Selenium (total) Vanadium (total) Zinc (total) Radium 226 pCi/g Radium 228 pCi/g Other*

*Include results of any hazardous waste characteristics tests performed for: 1) EP Toxicity, 2) Corrosivity, 3) Ignitability, and 4) Reactivity.

IL 532-0016



ANALYTICAL REPORT

Job Number: 500-19969-1

Job Description: Powerton Station

For:
Midwest Generation EME LLC
13082 E Manito Road
Pekin, IL 61554

Attention: Mr. Joe Heredia

Anni Staddmen

Approved for release Bornio M Stagetme Project Henager II 7/20/2009 A-29 PM

Bonnie M Stadelmann
Project Manager II
bonnie.stadelmann@testamericainc.com
07/28/2009

cc: Ms. Maria Race

These test results meet all the requirements of NELAC for accredited parameters.

The Lab Certification ID# is 100201. TestAmerica Portland OR00040

All questions regarding this test report should be directed to the TestAmerica Project Manager whose signature appears on this report. All pages of this report are integral parts of the analytical data. Therefore, this report should be reproduced only in its entirety.

Reporting limits are adjusted for sample size used, dilutions and moisture content if applicable.

TestAmerica Laboratories, Inc.
TestAmerica Chicago 2417 Bond Street, University Park, IL 60484
Tel (708) 534-5200 Fax (708) 534-5211 www.testamericainc.com



Job Narrative 500-J19969-1

Comments

No additional comments.

Receipt

All samples were received in good condition within temperature requirements.

Motok

No analytical or quality issues were noted.

General Chemistry

Method(s) 9071B: A deviation from the Standard Operating Procedure (SOP) occurred. Details are as follows: Due to the high moisture content of sample 500-19969-1, additional sodium sulfate was required to chemically dry the sample prior to analysis. Accordingly, the sample weight was reduced. This fact along with the higher correction for moisture content resulted in a higher reporting limit.

No other analytical or quality issues were noted.

EXECUTIVE SUMMARY - Detections

Client: Midwest Generation EME LLC

Job Number: 500-19969-1

Lab Sample ID Analyte	Client Sample ID	Result / Qualifier	Reporting Limit	Units	Method
500-19969-1	MCW BASIN				
Potassium Sodium Sulfate pH Phenolics, Total Re TOC Dup Percent Moisture Percent Solids Ammonia Nitrogen, Kjeldahl Phosphorus as P Biochemical Oxyge Chemical Oxygen I	n Demand	1900 7000 13000 9.04 1.5 3700 42 58 38 250 4100 70	77 150 4300 0.200 0.60 120 0.10 0.10 31 64 580 3.4 2200	mg/Kg mg/Kg mg/Kg su mg/Kg mg/Kg mg/Kg mg/Kg mg/Kg mg/Kg mg/Kg mg/Kg mg/Kg	6010B 6010B 9038 9045C 9066 Lloyd Kahn Moisture Moisture SM 4500 NH3 C SM 4500 NH3 C SM 4500 PE SM 5210B SM 5220C
TCLP Cadmium Soluble Alkalinity-Soluble		0.0094	0.0050	mg/L mg/Kg	60108 SM 2320B

METHOD SUMMARY

Client: Midwest Generation EME LLC

Job Number: 500-19969-1

Description	Lab Location	Method	Preparation Method
Matrix: Solid			
Metals (ICP) Toxicity Characteristic Leaching Procedure Preparation, Total Metals Preparation, Metals	TAL CHI TAL CHI TAL CHI TAL CHI	SW846 6010B	SW846 1311 SW846 3010A SW846 3050B
Mercury (CVAA) Toxicity Characteristic Leaching Procedure Preparation, Mercury	TAL CHI TAL CHI TAL CHI	SW846 7470A	SW846 1311 SW846 7470A
Acidity Delonized Water Leaching Procedure	TAL SAV TAL SAV	MCAWW 305.1	ASTM DI Leach
Cyanide Cyanide, Distillation	TAL CHI TAL CHI	SW846 9014	SW846 9010B
Sulfide, Acid Soluble and Insoluble (Titrimetric) Sulfide, Distillation (Acid Soluble and Insoluble)	TAL CHI TAL CHI	SW846 9034	SW846 9030B
Sulfate, Turbidimetric Anions, Ion Chromatography, 10% Wt/Vol	TAL CHI TAL CHI	SW846 9038	MCAWW 300_Prep
рН	TAL CHI	SW846 9045C	
Phenolics, Total Recoverable Distillation, Phenolics	TAL CHI TAL CHI	SW846 9066	Distill/Phenol
HEM HEM	TAL CHI TAL CHI	SW846 9071B	SW846 9071B
Organic Carbon, Total (TOC)	TAL CHI	NJDEP Lloyd K	ahn
Percent Moisture	TAL CHI	EPA Moisture	
Alkalinity Deionized Water Leaching Procedure	TAL CHI TAL CHI	SM SM 2320B	ASTM DI Leach
Ammonia Ammonia, Distillation	TAL CHI TAL CHI	SM SM 4500 N	H3 C SM SM 4500 NH3 B
Nitrogen-Total Kjeldahl Nitrogen, Total Kjeldahl	TAL CHI TAL CHI	SM SM 4500 No	org C MCAWW 351.3_Prep
Phosphorus Phosphorous, Total and Ortho	TAL CHI TAL CHI	SM SM 4500 P	E SM SM 4500 P B
BOD, 5-Day	TAL CHI	SM SM 5210B	
COD	TAL CHI TAL CHI	SM SM 5220C	SM SM 5220

Lab References:

TAL CH! = TestAmerica Chicago

TAL SAV = TestAmerica Savannah

TestAmerica Chicago

METHOD SUMMARY

Client: Midwest Generation EME LLC

Job Number: 500-19969-1

Description

Lab Location Method Preparation Method

Method References:

ASTM = ASTM International

EPA = US Environmental Protection Agency

MCAWW = "Methods For Chemical Analysis Of Water And Wastes", EPA-600/4-79-020, March 1983 And Subsequent Revisions.

NJDEP = New Jersey Department of Environmental Protection

SM = "Standard Methods For The Examination Of Water And Wastewater",

SW846 = "Test Methods For Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 And Its Updates.

TestAmerica Chicago

METHOD / ANALYST SUMMARY

Client: Midwest Generation EME LLC

Job Number: 500-19989-1

Method	Analyst	Analyst ID
SW846 6010B	Smith, Todd D	TDS
SW846 7470A	Klee, George O	GOK
MCAWW 305.1	Vasquez, Juana	JV
SW846 9014	Moore, Colleen L	CLM
SW846 9034	Moore, Colleen L	CLM
SW846 9038	Boyd, Cheryl L	CLB
SW846 9045C	Moore, Colleen L	CLM
SW846 9066	Ficarello, Peter M	PMF
SW846 9071B	Brogan, Mary T	MTB
NJDEP Lloyd Kahn	Deb, Khona	KD
EPA Moisture	Boyd, Cheryl L	CLB
SM SM 2320B	Moore, Colleen L	CLM
SM SM 4500 NH3 C	Brogan, Mary T	МТВ
SM SM 4500 Norg C	Brogan, Mary T	MTB
SM SM 4500 P E	Dillman, Jessica	JD
SM SM 5210B	Dillman, Jessica	JD
SM SM 5220C	Deb, Khona	KD

SAMPLE SUMMARY

Client: Midwest Generation EME LLC

Job Number: 500-19969-1

Lab Sample ID	Client Sample ID	Client Matrix	Date/Time Sampled	Date/Time Received
500-19969-1	MCW BASIN	Solid	07/14/2009 1310	07/15/2009 0930

SAMPLE RESULTS

TestAmerica Chicago

Mr, Joe Heredia Midwest Generation EME LLC 13082 E Manito Road Pekin, IL 61554

Job Number: 500-19969-1

Client Sample ID: MCW BASIN Lab Sample ID: 500-19969-1

Date Sampled: 07/14/2009 1310 Date Received: 07/15/2009 0930

Client Matrix: Solid

Analyte	Result/Qualifier	Unit	RL	Dilution
Method: TCLP-6010B		Date Analyzed:	07/20/2009 1736	
Prep Method: 3010A		Date Prepared:	07/20/2009 1015	
Arsenic	<0.050	mg/L	0.050	1.0
Barium	<0.50	mg/L	0.50	1.0
Cadmium	0.0094	mg/L	0.0050	1.0
Chromium	<0.025	mg/L	0.025	1.0
Lead	<0.050	mg/L	0.050	1.0
Selenium	<0.050	mg/L	0.050	1.0
Silver	<0.025	mg/L	0.025	1.0
Method: 6010B		Date Analyzed:	07/17/2009 1412	
rep Method: 3050B		Date Prepared:	07/17/2009 0752	
Potassium	1900	mg/Kg	77	1.0
Sodium	7000	mg/Kg	150	1.0
Method: TCLP-7470A		Date Analyzed:	07/21/2009 1329	
Prep Method: 7470A		Date Prepared:	07/21/2009 0900	
Mercury	<0 0020	mg/L	0.0020	1.0
Method: Soluble-305.1		Date Analyzed:	07/17/2009 0936	
Acidity	<200	mg/Kg	200	1.0
fiethod: 9014		Date Analyzed:	07/21/2009 1352	
Prep Method: 9010B		Date Prepared:	07/21/2009 1045	
Syanide, Total	<0.48	mg/Kg	0.48	1.0
Method: 9034		Date Analyzed:	07/24/2009 1610	
Prep Method: 9030B		Date Prepared:	07/24/2009 1040	
Sulfide	<40	mg/Kg	40	1,0
Method: 9038		Date Analyzed:	07/21/2009 2341	
Prep Method: 300_Prep		Date Prepared:	07/17/2009 0001	
Sulfate	13000	mg/Kg	4300	50
flethod: 9045C		Date Analyzed:	07/27/2009 1120	
ÞH	9,04	su	0.200	1,0
Nethod: 9066		Date Analyzed:	07/22/2009 0803	
Prep Method: Distill/Phenol		Date Prepared:	07/21/2009 1400	
Phenolics, Total Recoverable	1.5	mg/Kg	0.60	1.0
flethod: 9071B		Date Analyzed:	07/27/2009 1504	
Prep Method: 9071B		Date Prepared:	07/27/2009 0735	
HEM (Oil & Grease)	<1700	mg/Kg	1700	1.0

Mr. Joe Heredia Midwest Generation EME LLC 13082 E Manito Road Pekin, IL 61554 Job Number: 500-19969-1

Client Sample ID: MCW BASIN Lab Sample ID: 500-19969-1 Date Sampled: 07/14/2009 1310 Date Received: 07/15/2009 0930

Client Matrix: Solid

Analyte	Result/Qualifier	Unit	RL	Dilution
Method: Lloyd Kahn		Date Analyzed:	07/24/2009 0843	
TOC Dup	3700	mg/Kg	120	1.0
Method: Moisture		Date Analyzed:	07/15/2009 2210	
Percent Moisture	42	%	0.10	1.0
Method: Soluble-SM 2320B		Date Analyzed:	07/20/2009 1229	
Alkalinity	1400	mg/Kg	510	1.0
Method: SM 4500 NH3 C		Date Analyzed:	07/16/2009 1436	
Prep Method: SM 4500 NH3 B		Date Prepared:	07/16/2009 0745	
Ammonia	38	mg/Kg	31	1.0
Method: SM 4600 Norg C		Date Analyzed:	07/16/2009 1443	
Prep Method: 351.3_Prep		Date Prepared:	07/16/2009 0730	
Nitrogen, Kjeldahl	250	mg/Kg	64	1.0
Method: SM 4500 P E		Date Analyzed:	07/20/2009 1235	
Prep Method: SM 4500 P B		Date Prepared:	07/17/2009 1339	
Phosphorus as P	4100	mg/Kg	580	50
Method: SM 5210B		Date Analyzed:	07/22/2009 1326	
Biochemical Oxygen Demand	70	mg/Kg	3.4	1.0
Method: SM 5220C		Date Analyzed:	07/24/2009 1352	
Prep Method: SM 5220		Date Prepared:	07/24/2009 0900	
Chemical Oxygen Demand	22000	mg/Kg	2200	10

DATA REPORTING QUALIFIERS

Client: Midwest Generation EME LLC

Job Number: 500-19969-1

Lab Section	Qualifier	Description
General Chemistry		ALLE HALL ACTES NOT
	4	MS, MSD: The analyte present in the original sample is 4 times greater than the matrix spike concentration; therefore, control limits are not applicable.

APPENDICES

Appendix A: Test Pit Photo Log and Excavation Logs

Appendix B: Hydrologic Analysis

B1: Summary of Stormwater Modeling Results

B2: Sanford Gasification Plant Site Hydrologic Assessment - OU3 Plus

OU1 (May 2008)

B3: Compensating Flood Storage Calculations

Appendix C: Remedial Quantity and Material Balance Calculations

SHEETS

TS	Site Location Map/Title Sheet
C010	Site Plan Existing Conditions OU1
C015	Utility Relocate Plan OU1
C020	Site Preparation Plan OU1
C021	Environmental Management Plan OU1
C022	Preliminary ISS Pilot Test Layout Plan
C030	Proposed Surface Water Diversion Plan OU1
C032	Drainage Improvement Grading Plan OU1 (Pond) (Not Included)
C033	Drainage Improvement Grading Plan OU1
C034	Plan & Profile OU1
C040	Surface Soil Removal Plan OU1
C050	ISS Construction Plan OU1
C051	ISS Phasing/Sequencing Plan OU1
C055	ISS Swell Management Plan OU1
C060	Site Restoration Plan OU1
C070	Sections and Details OU1 (Not Included)
C110	Site Plan Existing Conditions OU3
C115	Utility Relocate Plan OU3
C120	Site Preparation Plan OU3
C121	Environmental Management Plan OU3
C130	Proposed Surface Water Diversion Plan OU3
C140	Site Remediation Plan OU3 South
C145	Site Remediation Plan OU3 North
C150	Drainage Improvement Grading Plan OU3 South
C151	Plan & Profile OU3 - 3rd to 2nd St.
C152	Plan & Profile OU3 - 2 nd to 1 st St.
C155	Surface Water Construction Plan OU3 North
C160	Site Restoration Plan OU3 South (Not Included)
C165	Site Restoration Plan OU3 North
C170	Sections and Details OU3 (Not Included)

	lestAmerico	Derica	OI.	Cortect	و ا	Kary			Contest Contest			Chail	Tof Custoal	Chain of Custody Record
	THE LEADER IN ENVIR	RONMENTAL TESTI	S	8 9 9	֓֞֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓֓	27 G		2.5	Jumper J.				to Job F	
Cart Prints 1 There is a second control of the con	LEPECITYE 771A NEW ZIP CODE	09 CUK IS 60484		Feet		7 3 3	1443	1 1				a: 1º	reperture 'C of Code:	Ξ
100 100	an Million Gran	POLIDIAN CLAMPS	igad 9				3/1017					1	275	Preservéns Kay
CELY ST	Pojed Have	B451~				Paterneter	W		142.	2910		1	(= 1)	2. H2804, Coel to # 3, H401, Coel to #
	Į		45				J-1k	7		dimo	r-	10241, 19 ⁶ 191		A NaOH, Cadin 4- 5. NaOHO, Coolin 4- 8. Ordin 6-
	2			HOELM4	3		שינים	17.00	4	t we				7. None B. Other
	CISTES			Same	Dig.				410	NO 0	14 14 10 14 14 10 14 16 16 16 16 16 16 16 16 16 16 16 16 16	00.		
	en en			Cade	<u>2</u>	_			5	3	V	기		Corrects
	MCW			7140	1701:1	— F	×	\parallel				χ.		
Detail States Dey Desair				OV.		-	М			531		(F)	tra tra	ès
			R	7	è	-				7/2				8 £
Days 2-30pt 2-3			1999	27	18 E			10		22				30
Days		ir ir iii		13		25		III)		sR JH			1	9€
Days		100	X T		9	38.	81					4)11		e 51
Days	- 9	1000		31.5 256	3/I	23		I -		ta E		35)		đ
Days	 32	165 630 1610	£	i h	IX.				0;		11 G	PER		
Dors 5 Days 15 Days				er Ser		rati			/ / · · · · · · · · · · · · · · · · · ·	4				
Days Days Days) Days — 15 Days — 16 Days Days Days Days Days Days Days Days			70		13 33		12.		12	EX.	92			
Pri tue Contract Plant P	Terranou of Then Required (Studies	TO days	- 15 Days		1	Sarrate Chap	E C	X	43.45	_Active for _		resy to assessed Esse	ins are rately	f Bun (reosit)
Merit key Campany Dala Ties Received by General Data Tina Hand Defound Comments: Merit key Office Sastement So – Salida Maria Comments: Let Label San Tina Hand Defound Comments: Merit key Office Comments: Let Label San Tina Hand Defound Comments: Merit key Office Comments: Let Label San Tina Hand Defound Comments: Let Label San Tina Hand Defound Comments: Merit key Comments: Let Label San Tina Hand Defound Comments: Let Label San Tina Hand Defound Comments: Merit key Comments: Let Label San Tina Hand Defound Comments: Let		Awen	12	1405		Kom K	Received By	X		, etc	15/05			
Merit Key Chent Comments W. Sackman Sec. Sackman Chent Comments: L. Dackman Sec. Sackman Chent Comments: L. Dackman Chent Comments: L. Dackman Chent Comments: Dackman Chent	Pull quitate By	Campany	e.				Peceleddy	,	Contrary		Cleb	ref.	act .	
september 8E - Sacken 1 SO - Sail I - Lucibrate So - Sail So - Sai			1				_			9			Hand Delivery	2
	activistic of the control of the con	- Sadnerit - Sal Luciera - Woe r - Orethig Neter - Oter												

PERMITTED STATE

Login Sample Receipt Check List

Client: Midwest Generation EME LLC

Job Number: 500-19969-1

Login Number: 19969 Creator: Lunt, Jeff T

List Number: 1

List Source: TestAmerica Chicago

Question	2011011	T/F/NA	Comment	avit Said
Radioactivity either was not measured or, if measure background	d, is at or below	True	53346	133
The cooler's custody seal, if present, is intact.		True		
The cooler or samples do not appear to have been of tampered with.	ompromised or	True		
Samples were received on ice.		False		
Cooler Temperature is acceptable.		True		
Cooler Temperature is recorded.		True		
COC is present.		True		
COC is filled out in ink and legible.		True		
COC is filled out with all pertinent information.		True		
There are no discrepancies between the sample IDs the COC.	on the containers and	True		
Samples are received within Holding Time.		True		
Sample containers have legible labels.		True		
Containers are not broken or leaking.		True		
Sample collection date/times are provided.		True		
Appropriate sample containers are used.		True		
Sample bottles are completely filled.		True		
There is sufficient vol. for all requested analyses, inc MS/MSDs	l. any requested	True		
VOA sample vials do not have headspace or bubble diameter.	is <6mm (1/4") in	True		
If necessary, staff have been informed of any short h needs	old time or quick TAT	True		
Multiphasic samples are not present.		True		
Samples do not require splitting or compositing.		True		
is the Field Sampler's name present on COC?		True	10.7	
Sample Preservation Verified		True		

Login Sample Receipt Check List

Client: Midwest Generation EME LLC


Job Number: 500-19969-1


Login Number: 19969 Creator: Conner, Keaton


List Number: 1


List Source: TestAmerica Savannah List Creation: 07/16/09 01:39 PM

Question	70,000	1.1	T/F/NA	Comment	
Radioactivity either was not measured or, background	if measured	, is at or below	N/A	THE THE H	
The cooler's custody seal, if present, is int	act.		True		
The cooler or samples do not appear to he tampered with.	ive been co	mpromised or	True		
Samples were received on ice.			True		
Cooler Temperature is acceptable.			True		
Cooler Temperature is recorded.			True		
COC is present.			True		
COC is filled out in ink and legible.			True		
COC is filled out with all pertinent informat	ion.		True		
There are no discrepancies between the s the COC.	ample IDs o	n the containers and	l True		
Samples are received within Holding Time	9		True		
Sample containers have legible tabets.			True		
Containers are not broken or leaking.			True		
Sample collection date/times are provided			True		
Appropriate sample containers are used.			True		
Sample bottles are completely filled.			True		
There is sufficient vol. for all requested and MS/MSDs	alyses, incl.	any requested	True		
VOA sample vials do not have headspace diameter.	or bubble is	<6mm (1/4") in	N/A		
If necessary, staff have been informed of a needs	ny short hol	d time or quick TAT	True		
Multiphasic samples are not present.	¥.		N/A		
Samples do not require splitting or compos	iting.		N/A		
is the Field Sampler's name present on CO	C?		True		
Sample Preservation Verified			True		









FOR IEPA USE: LOG # DATE RECEIVED:

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL PERMIT SECTION

Springfield, Illinois 62706


SCHEDULE J INDUSTRIAL TREATMENT WORKS CONSTRUCTION OR PRETREATMENT WORKS

		0144				575144		
	1.2.1	SW	9		T24N	R5W		
		er Section	Section		wnship	Range		P.M.
			deg		22	80	_ sec.	"NORTH
		89		40	min	90	sec.	"WEST
			le Map (7.5 or 15					
VARE	RATIVE DESCRIP	LION AND SCH	EMATIC WASTE	FLOW DIAG	RAM: (see inst	ructions)		
Durir	ng annual maint	enance of the P	Powerton Power	Station boil	ers, cleaning/v	vash water flow	s to the	metal cleanii
basir	n periodically be	ween March ar	nd June of each	year, as sh	own on attach	ed waste flow d	iagram.	
2.1	PRINCIPAL PR	DUCTS:						
	electrical power	r						
.2	PRINCIPAL RA	V MATERIALS:			- W			
	coal						525	
	coal							
ESC		ATMENT FACIL	ITIES		Į.			
	CRIPTION OF TRI						-	
	CRIPTION OF TRI	gram through all	treatment units sh	- 1000	olumes, detentio	n times, organic Ic	eadings, 8	_
1,1	CRIPTION OF TRI Submit a flow dia weir overflow rat	gram through all e, and other pert	treatment units sh inent design data.	. Include hyd	olumes, detentio	n times, organic Ic	eadings, s	ig systems.
.1	CRIPTION OF TRI Submit a flow dia weir overflow rai Waste Treatmen	gram through all e, and other pert t Works is: Batc	treatment units sh inent design data. th	. Include hyd uous 🗵	olumes, detentio	n times, organic Ic	eadings, s	ig systems.
3.1 3.2 3.3	CRIPTION OF TRI Submit a flow dia weir overflow rat Waste Treatmen Submit plans an	gram through all e, and other pert t Works is: Batc I specifications f	treatment units shinent design data. Continuor proposed consi	. Include hyd uous 図 truction.	olumes, detentio raulic profiles ar . No. of Batche	n times, organic Ic	eadings, s	ig systems.
3.2 3.3 3.4	CRIPTION OF TRI Submit a flow dia weir overflow rai Waste Treatmer Submit plans an Discharge is: E:	gram through all e, and other pert t Works is: Batc d specifications for isting 🗵	treatment units shinent design data. Continuor proposed consistential begin on	. Include hyd uous 🗵 truction.	olumes, detentio raulic profiles ar , No. of Batche	n times, organic lond description of s	eadings, a monitorin No. of Sh	ig systems lifts/day
3.1 3.2 3.3 3.4 DIREC	CRIPTION OF TRI Submit a flow dia weir overflow rat Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE	gram through all a, and other pertit Works is: Batc if specifications finating 🖾 STO: Receiving	treatment units shinent design data. Continuor Continuor proposed consi; Will begin on Stream Mu	. Include hyduous 🗵 truction.	olumes, detentio raulic profiles ar , No. of Batche iry Sewer . A	n times, organic lond description of s	eadings, a monitorin No. of Sh	ig systems lifts/day
3.1 3.2 3.3 3.4 DIREC	CRIPTION OF TRI Submit a flow dia weir overflow rai Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE	gram through all e, and other pert t Works is: Batc d specifications fi isting STO: Receiving orm sewer are inc	treatment units shinent design data. Continior proposed const; Will begin on Stream Mundicated complete	. Include hyduous X truction. nicipal Sanitathe following	olumes, detentio raulic profiles ar , No. of Batche	n times, organic lond description of a s/day, i	eadings, a monitorin No. of Sh	ig systems. ifts/day al combined s
3.1 3.3 3.4 DIREC	CRIPTION OF TRI Submit a flow dia weir overflow rai Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE	gram through all e, and other pert t Works is: Batc d specifications fi isting STO: Receiving orm sewer are inc	treatment units shinent design data. Continior proposed const; Will begin on Stream Mundicated complete	. Include hyduous X truction. nicipal Sanitathe following	olumes, detentio raulic profiles ar , No. of Batche	n times, organic lond description of a s/day, i	eadings, a monitorin No. of Sh	ig systems. ifts/day al combined s
3.2 3.3 3.4 rece lame	CRIPTION OF TRI Submit a flow dia weir overflow rat Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE eiving stream or st of receiving stream ary to	gram through all a, and other pert tworks is: Batc I specifications from STO: Receiving STO: Receiving orm sewer are incomed Old Intake Communications.	treatment units shinent design data. ch, Continuor proposed consi; Will begin on g Stream 🗷 Mui dicated complete Channel	. Include hydunous IX truction. nicipal Sanitathe following: ; tributary	olumes, detention raulic profiles and No. of Batche lary Sewer . A tributary to	n times, organic lond description of is/day, i	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.3 3.4 Precelame ributa	CRIPTION OF TRI Submit a flow dia weir overflow rat Waste Treatmen Submit plans an Discharge is: E: CT DISCHARGE eiving stream or st of receiving strea ary to treatment works s	gram through all e, and other pert t Works is: Batc I specifications from STO: Receiving STO: Receiving orm sewer are income Old Intake Couplet to flooding	treatment units shinent design data. ch Continuor proposed consi; Will begin on g Stream Mudicated complete channel 7 Yes No 5	. Include hyduous Include hyduous Include hydruction. nicipal Sanitathe following: ; tributary	olumes, detention raulic profiles and No. of Batche rry Sewer . And tributary to	n times, organic lond description of is/day, i	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.3 3.4 Precelame ributa	CRIPTION OF TRI Submit a flow dia weir overflow rat Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE eiving stream or st of receiving stream ary to	gram through all e, and other pert t Works is: Batc I specifications from STO: Receiving STO: Receiving orm sewer are income Old Intake Couplet to flooding	treatment units shinent design data. ch Continuor proposed consi; Will begin on g Stream Mudicated complete channel 7 Yes No 5	. Include hyduous Include hyduous Include hydruction. nicipal Sanitathe following: ; tributary	olumes, detention raulic profiles and No. of Batche rry Sewer . And tributary to	n times, organic lond description of is/day, i	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.3 3.4 Precelame ributa	CRIPTION OF TRI Submit a flow dia weir overflow rat Waste Treatmen Submit plans an Discharge is: E: CT DISCHARGE eiving stream or st of receiving strea ary to treatment works s	gram through all e, and other pert t Works is: Batc I specifications from STO: Receiving STO: Receiving orm sewer are income Old Intake Couplet to flooding	treatment units shinent design data. Ch Continuor proposed consi; Will begin on Stream Mundicated complete Channel Yes No 5	. Include hyduous Include hyduous Include hydruction. nicipal Sanitathe following: ; tributary	olumes, detention raulic profiles and No. of Batche rry Sewer . And tributary to	n times, organic lond description of is/day, i	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
.1 .2 .3 .4 PREC rece lame ibuta ; the	CRIPTION OF TRI Submit a flow dia weir overflow rat Waste Treatmen Submit plans an Discharge is: E: CT DISCHARGE eiving stream or st of receiving strea ary to treatment works s	gram through all e, and other pert t Works is: Batc I specifications from STO: Receiving STO: Receiving orm sewer are income Old Intake Couplet to flooding	treatment units shinent design data. Ch Continuor proposed consi; Will begin on Stream Mundicated complete Channel Yes No 5	. Include hyduous Include hyduous Include hydruction. nicipal Sanitathe following: ; tributary	olumes, detention raulic profiles and No. of Batche rry Sewer . And tributary to	n times, organic lond description of is/day, i	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.3 3.4 Frece I rece I rece I rece I rece I rece I rece	Submit a flow dia weir overflow rat Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE siving stream or st of receiving stream treatment works an ent works datum)	gram through all a, and other pert tworks is: Batc I specifications from STO: Receiving The Store I should be seen and what provisions and what provisions and what provisions are seen the seen are seen as the seen as the seen are seen as the see	treatment units shinent design data. ch Continuor proposed consi; Will begin on Continuor proposed consi; Will begin on Continuor proposed consi; Stream Mundicated complete channel The Yes No Signs have been mines.	Include hyduous IX truction. Inclipat Sanitathe following: tributary: If so, whade to elimin	olumes, detention raulic profiles and No. of Batche rry Sewer . And tributary to	n times, organic lond description of is/day, i	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.3 3.4 INREC rece lame ributa s the eatm	Submit a flow dia weir overflow rat Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE siving stream or st of receiving stream tworks arent works datum)	gram through all e, and other pert t Works is: Batc d specifications fi isting STO: Receiving orm sewer are inc Old Intake C ubject to flooding and what provisi	treatment units shinent design data. ch Continuor proposed consi; Will begin on g Stream Mundicated complete channel 7 Yes No 5 ions have been materials.	. Include hyduous Include Include Include Include Including Includ	olumes, detention raulic profiles and No. of Batche ary Sewer . And tributary to the to the maximulate the flooding.	n times, organic lond description of is/day, i	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.3 3.4 INREC rece lame ributa s the eatm	Submit a flow dia weir overflow rat Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE siving stream or st of receiving stream treatment works an ent works datum)	gram through all e, and other pert t Works is: Batc d specifications fi isting STO: Receiving orm sewer are inc Old Intake C ubject to flooding and what provisi	treatment units shinent design data. ch Continuor proposed consi; Will begin on g Stream Mundicated complete channel 7 Yes No 5 ions have been materials.	. Include hyduous Include Include Include Include Including Includ	olumes, detention raulic profiles and No. of Batche rry Sewer . And tributary to	n times, organic lond description of is/day, i	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.2 3.3 3.4 DIRECT recelame ributa s the reatm	CRIPTION OF TRI Submit a flow dia weir overflow ra Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE eiving stream or st of receiving strea ary to treatment works a ment works datum) OXIMATE TIME S of Construction 10 tion Schedule not	gram through all e, and other pert t Works is: Batc d specifications for isting SI S.TO: Receiving orm sewer are in m. Old Intake Co ubject to flooding and what provisi CHEDULE: Est /15/09 in service btw 7/	treatment units shinent design data. ch Continior proposed const; Will begin on Stream Mundicated complete channel ? Yes No sinns have been manual constructions.	Include hyduous IX truction. nicipal Sanita the following: tributary If so, whade to eliminate the conschedule: Date of Compare Operating the conschedule:	olumes, detention raulic profiles as No. of Batche ry Sewer A tributary to Illinoto at is the maximulate the flooding opletion 12/31/	n times, organic lond description of is/day, is/day, is/dunicipal storm of nois River Im flood elevation hazard?	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.2 3.3 3.4 PIREC rece dame ributa s the eatm	Submit a flow dia weir overflow rat Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE eiving stream or state of receiving stream or treatment works a ment works datum) CXIMATE TIME Soft Construction 10 design load to be	gram through all e, and other pert t Works is: Batc d specifications for isting SI S.TO: Receiving orm sewer are in m. Old Intake Co ubject to flooding and what provisi CHEDULE: Est /15/09 in service btw 7/	treatment units shinent design data. ch Continior proposed const; Will begin on Stream Mundicated complete channel ? Yes No sinns have been manual constructions.	Include hyduous IX truction. nicipal Sanita the following: tributary If so, whade to eliminate the conschedule: Date of Compare Operating the conschedule:	olumes, detention raulic profiles as No. of Batche ry Sewer A tributary to Illinoto at is the maximulate the flooding opletion 12/31/	n times, organic lond description of is/day, is/day, is/dunicipal storm of nois River Im flood elevation hazard?	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.2 3.3 3.4 DIRECTOR Trace I are a tributate in the treatment of the trace in t	CRIPTION OF TRI Submit a flow dia weir overflow ra Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE eiving stream or st of receiving strea ary to treatment works a ment works datum) OXIMATE TIME S of Construction 10 tion Schedule not	gram through all e, and other pert t Works is: Batc d specifications for isting SI S.TO: Receiving orm sewer are in m. Old Intake Co ubject to flooding and what provisi CHEDULE: Est /15/09 in service btw 7/	treatment units shinent design data. ch Continior proposed const; Will begin on Stream Mundicated complete channel ? Yes No sinns have been manual constructions.	Include hyduous IX truction. nicipal Sanita the following: tributary If so, whade to eliminate the conschedule: Date of Compare Operating the conschedule:	olumes, detention raulic profiles as No. of Batche ry Sewer A tributary to Illinoto at is the maximulate the flooding opletion 12/31/	n times, organic lond description of is/day, is/day, is/dunicipal storm of nois River Im flood elevation hazard?	eadings, s monitorin No. of Sh	g systems, lifts/day al combined s
3.1 3.2 3.3 3.4 DIRECTORNAME Treatments APPR	Submit a flow dia weir overflow rat Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE siving stream or st of receiving stream tworks arent works datum)	gram through all e, and other pert t Works is: Batc d specifications fr isting STO: Receiving orm sewer are inc Old Intake C ubject to flooding and what provisi	treatment units shinent design data. ch Continuor proposed consi; Will begin on g Stream Mundicated complete channel 7 Yes No 5 ions have been materials.	. Include hyduous Include Include Include Include Including Includ	olumes, detention raulic profiles and No. of Batche ary Sewer . And tributary to the to the maximulate the flooding.	n times, organic lond description of is/day, i	eadings, s monitorin No. of Sh	g systems lifts/day al combin
3.1 3.2 3.3 3.4 DIREC frece Name ributa s the reatm	Submit a flow dia weir overflow rat Waste Treatmer Submit plans an Discharge is: E: CT DISCHARGE eiving stream or state of receiving stream or treatment works a ment works datum) CXIMATE TIME Soft Construction 10 design load to be	gram through all e, and other pert t Works is: Batc d specifications for isting SI S.TO: Receiving orm sewer are in m. Old Intake Co ubject to flooding and what provisi CHEDULE: Est /15/09 in service btw 7/	treatment units shinent design data. ch Continior proposed const; Will begin on Stream Mundicated complete channel ? Yes No sinns have been manual constructions.	Include hyduous IX truction. nicipal Sanita the following: tributary If so, whade to eliminate the conschedule: Date of Compare Operating the conschedule:	olumes, detention raulic profiles as No. of Batche ry Sewer A tributary to Illinoto at is the maximulate the flooding opletion 12/31/	n times, organic lond description of is/day, is/day, is/dunicipal storm of nois River Im flood elevation hazard?	eadings, s monitorin No. of Sh	g systems. ifts/day al combined :

7.4		MGD	re:		
1.7	Design Minimum Flow Rate NA	MGD.			
7.5	Minimum 7-day, 10-year low flow NA	cfs	NA	MGD.	
	Minimum 7-day, 10-year flow obtained from	m <u>NA</u>			
7.6	Dilution Ratio NA				
FLO\	W TO TREATMENT WORKS (if existing):				
8.1	Flow (last 12 months)				
	8.1.1 Average Flow <u>0.89</u>	MGD			
	8.1.2 Maximum Flow <u>1,19</u>	MGD		05 .05	
8.2	Equipment used in determining above flo				
Has a	preliminary engineering report for this pro				
Yes [☐ No 図 . If so, when was it submitted	and approved. [Date Submitted		
		100	Certification #	4676	
		200	Dated		
. List F	ermits previously issued for the facility:				
	ribe provisions for operation during continger	icies such as pow	ver tailures, noocin	g, peak losos, equipment lailure	, maintenance
The	s and other emergencies. re is no equipment in the basin. Influer	nt pumped to be	- 1 9=11EE		
The	s and other emergencies.	nt pumped to be	- 1 9=11EE		
Thei malf	s and other emergencies. re is no equipment in the basin. Influer unction, the flow of influent to the basin	nt pumped to be n stops.	asin, so in the ev		
The malf	s and other emergencies. re is no equipment in the basin. Influer unction, the flow of influent to the basin older and submit Schedule G if sludge disposes.	nt pumped to be n stops.	asin, so in the ev		
Thei malf Comp	s and other emergencies. re is no equipment in the basin. Influer unction, the flow of influent to the basin better and submit Schedule G if sludge dispute CHARACTERISTICS: Schedule N must	nt pumped to be n stops. osal will be require st be submitted.	esin, so in the every second to the every seco	vent of power failure or equi	pment
The malf	s and other emergencies. The is no equipment in the basin. Influer function, the flow of influent to the basin place and submit Schedule G if sludge disposed in the control of the contr	nt pumped to be n stops. osal will be require st be submitted.	esin, so in the every second to the every seco	vent of power failure or equi	pment
The malf	s and other emergencies. re is no equipment in the basin. Influer unction, the flow of influent to the basin better and submit Schedule G if sludge dispute CHARACTERISTICS: Schedule N must	nt pumped to be n stops. osal will be require st be submitted.	esin, so in the every second to the every seco	vent of power failure or equi	pment
The malf	s and other emergencies. The is no equipment in the basin. Influer function, the flow of influent to the basin place and submit Schedule G if sludge disposed in the control of the contr	nt pumped to be n stops. osal will be require st be submitted.	esin, so in the every second to the every seco	vent of power failure or equi	pment
The malf	s and other emergencies. The is no equipment in the basin. Influer function, the flow of influent to the basin place and submit Schedule G if sludge disposed in the control of the contr	nt pumped to be n stops. psal will be required to be submitted.	esin, so in the every second to the every seco	vent of power failure or equi	pment
Thei malf	s and other emergencies. The is no equipment in the basin. Influent to the basin unction, the flow of influent to the basin plete and submit Schedule G if sludge disposed and submit Schedule G if sludge disposed in the control of	nt pumped to be a stops. osal will be required to be submitted. ATION: List name	esin, so in the evered by this facility.	vent of power failure or equi	pment
The malf	s and other emergencies. Te is no equipment in the basin. Influer function, the flow of influent to the basin plete and submit Schedule G if sludge disposete and submit Schedule G if sludge disposete and submit Schedule S Schedule N must at MENT WORKS OPERATOR CERTIFICATE (See attached certification)	nt pumped to be a stops. osal will be required to be submitted. ATION: List name	esin, so in the evered by this facility.	vent of power failure or equip	pment
The malf	s and other emergencies. Te is no equipment in the basin. Influer function, the flow of influent to the basin bete and submit Schedule G if sludge disposete G is sludge disposete and submit Schedule G if sludge disposete G is sludge G is sludge disposete G is sludge disposete G is sludge G is sludg	nt pumped to be a stops. osal will be required to be submitted. ATION: List name	esin, so in the evered by this facility.	vent of power failure or equi	pment

76

IL 532-0018 WPC 158



AUSCHE - THEFT

This Agency is authorized to require this information under Illinois Revised Statutes, 1979, Chapter 111 1/2, Section 1039. Disclosure of this information is required under that section. Failure to do so may prevent this form from being processed and could result in your application being denied.

1. Name of Project Powerton Metal Cleaning Basin Liner Replacement

EXISTING

2. FLOW DATA

For IEPA Use:	
LOG#	
DATE RECEIVED:	A SMAN

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL PERMIT SECTION Springfield, Illinois 62794-9276

SCHEDULE N WASTE CHARACTERISTICS

PROPOSED-DESIGN

		0	NA NA	
2.2 Maximum Daily Flow (gpo	d)1,1 ⁻	90,000	NA NA	25° 75°
2.3 TEMPERATURE		1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		
		100 A		Max. Temp.
		Avg. Effluent Max. I		Effluent Outside Mixin
<u>Year</u>	FIE CONTRACTOR	11 5 To 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1		emp F. Zone F
SUMMER	NA	NA NA		IA NA
WINTER	NA	NA NA		IA NA NA
2.4 Minimum 7-day, 10-year t	now: NA	cle NA MCD		ST FAME
2.5 Dilution Ratio: NA	14°, S	CISIVIIVIGD.		
2.6 Stream flow rate at time	40.	A cfs NA	MGD.	
CHEMICAL CONSTITUENT E		organ Earliery Super CAS		posed Permitted Conditions
		(CA) (Mar) (A)		A STATE OF THE PARTY OF THE PAR
Type of sample:); ı <u>zı</u> compo	site (Number of sa	mpies per day)
see instructions for analyses	required)			1
	RAW WASTE	TREATED EFFLUENT	UPSTREAM	DOWNSTREAM SAMPLE
CONSTITUENT	(mg/l)	Avg. (mg/l) Max.	(mg/l)	(mg/l)
Ammonia Nitrogen (as N)	NA	NA	INA	
		145	INA	NA
Arsenic (total)	NA	NA	NA NA	NA NA
	1	975L		1007-6
Arsenic (total)	NA	NA	NA	NA
Arsenic (total) Barium	NA NA	NA NA	NA NA	NA NA
Arsenic (total) Barium Boron	NA NA NA	NA NA NA	NA NA NA	NA NA NA
Arsenic (total) Barium Boron BOD ₅	NA NA NA NA	NA NA NA	NA NA NA NA	NA NA NA
Arsenic (total) Barium Boron BOD ₅ Cadmium	NA NA NA NA	NA NA NA NA	NA NA NA NA	NA NA NA NA
Arsenic (total) Barium Boron BODs Cadmium Carbon Chloroform Extract	NA NA NA NA NA NA	NA NA NA NA NA	NA NA NA NA NA	NA NA NA NA NA NA

CONSTITUENT	RAW WASTE (mg/l)	TREATED EFFLUENT Avg. (mg/l) Max.	UPSTREAM (mg/l)	DOWNSTREAM SAMPLES (mg/l)
Copper	NA	<0.010 / <0.010	NA	NA
Cyanide (total)	NA	NA	NA	NA
Cyanide (readily released @ 150° F & pH 4.5)	NA	NA	NA	NA
Dissolved Oxygen	NA	NA	NA	NA
Fecal Coliform	NA	NA	NA	NA
Fluoride	NA	NA	NA	NA
Hardness (as Ca CO ₃)	NA	NA	NA	NA
Iron (total)	NA	0.047 / 0.210	NA	NA
Lead	NA	NA	NA	NA
Manganese	NA	NA	NA	NA II
MBAS	NA	NA	NA	NA
Mercury	NA	NA	NA	NA =
Nickel	NA	NA	NA	NA
Nitrates (as N)	NA	NA	NA	NA
Oil & Grease (hexane solubles or equivalent)	NA	<5.6 / <6.0	NA	NA
Organic Nitrogen (as N)	NA	NA	NA	NA
pH	NA	NA	NA	NA
Phenois	NA	NA	NA	NA
Phosphorous (as P)	NA	NA	NA	NA
Radioactivity	NA	NA	NA	NA
Selenium	NA	NA	NA	NA
Silver	NA	NA	NA	NA
Sulfate	NA	NA	NA	NA
Suspended Solids	NA	<4.9 / 11.0	NA	NA
Total Dissolved Solids	NA	NA	NA	NA •
Zinc	NA	NA	NA	NA
Others				
47				

IL 532-0019 WPC 159

Date!

1,580/

をのう この数を ちゃん

ない

(1)

18/18/

Section.

		25 /AST			
				**	
				261	12
		4		55	
	893	100			
				1.0	Mary Mary
					373
		- 304			
	-11				
				W	
				110	
			1116		
					G 10 12 13 15 15
			R	-	100
				NA.	
				100	
1					
		1			
		-			

APPENDIX B PHOTOGRAPHS

PHOTOGRAPH LOG

Powerton Power Station Metal Cleaning Basin Midwest Generation, LLC Pekin, Illinois

Photog Num		Photograph Description	
1		South end of Metal Cleaning Basin looking north on June 22, 2009.	
2	2.	West side of Metal Cleaning Basin looking southeast on June 22, 2009	
3	3.	North end of Metal Cleaning Basin looking northeast on June 22, 2009.	
4	i.	South end of Metal Cleaning Basin looking southwest on June 22, 2009.	
5	i.	Looking down concrete access ramp on June 22, 2009.	
6	5.	Northwest corner looking east on June 22, 2009.	



Photo I



Photo 2




Photo 3




Photo 4



Photo 5




Photo 6

Page 1 1916 P

APPENDIX C

SPECIFICATION SECTION 02600

SECTION 02600 HIGH DENSITY POLYETHYLENE (HDPE) GEOMEMBRANE

PART 1 - GENERAL

1.01 WORK INCLUDES

A. Furnish all labor, materials, tools, supervision, transportation, and installation equipment necessary for installation of 60-mil High Density Polyethylene (HDPE) geomembrane, as specified herein, and as shown on Contract Drawings.

1.02 REFERENCE STANDARDS

- A. ASTM D5641 Standard Practice for Geomembrane Seam Evaluation by Vacuum Chamber
- B. ASTM D5820 Standard Practice for Pressurized Air Channel Evaluation of Dual Seamed Geomembranes
- C. ASTM D6392 –Test Method for Determining the Integrity of Nonreinforced Geomembrane Seams Produced Using Thermo-Fusion Methods.
- D. ASTM D7007 Standard Practice for Locating Leaks in Geomembranes Covered with Water or Earthen Materials.
- E. GRI Test Method, GM 13 Test Methods, Test Properties and Testing Frequency for High Density Polyethylene (HDPE) Smooth and Textured Geomembranes
- F. GRI Test Method, GM 14 Selecting Variable Intervals for Taking Geomembrane Destructive Seam Samples Using the Method of Attributes.
- G. GRI Test Method, GM 19 Seam Strength and Related Properties of Thermally Bonded Polyolefin Geomembranes.

1.03 DEFINITIONS

- A. Geomembrane Installer: hired by Contractor or Owner responsible for field handling, transporting, storing, deploying, seaming and testing of the geomembrane seams.
- B. Geomembrane Manufacturer: hired by Geomembrane Installer, Contractor, or Owner to provide HDPE geomembrane.
- C. Leak Location Contractor: hired by Contractor or Owner and responsible for locating potential holes in the installed geomembrane using electrical methods.
- D. Geosynthetic Quality Assurance Consultant: Consultant, independent from the Manufacturer, and Installer, responsible for field oversight of geosynthetics installation, and related testing, usually under the direction of the Owner.

1965 Section 02600 HDPE Geomembrane

- D. Geosynthetic Quality Assurance Laboratory (Testing Laboratory): Laboratory, independent from the Manufacturer and Installer, responsible for conducting laboratory tests on samples of geosynthetics obtained at the site or during manufacturing, usually under the direction of the Owner.
- D. Lot: A quantity of resin (usually the capacity of one rail car) used in the manufacture of geomembranes. Finished roll will be identified by a roll number traceable to the resin lot used.
- E. Resin Supplier: selected by Geomembrane Manufacturer to provide resin used in manufacturing geomembrane.
- F. Panel: Unit area of a geomembrane that will be seamed in the field that is larger than $100 {\rm ft}^2$.
- G. Patch: Unit area of a geomembrane that will be seamed in the field that is less than $100 \, \mathrm{ft}^2$.
- H. Subgrade Surface: Soil Layer surface which immediately underlies the geosynthetic material(s).

1.04 QUALITY ASSURANCE

A. Qualifications:

- Geomembrane Manufacturer shall have a minimum of 5 years of continuous experience manufacturing HDPE geomembrane totaling 1,000,000 square feet.
- 2. Geomembrane Installer:
 - a. 5 years of continuous experience in installation of HDPE geomembrane.
 - Experience totaling a minimum of 5,000,000 square feet of installed HDPE geomembrane on some combination of at least 10 completed facilities.
 - c. Personnel performing seaming operations qualified by experience or by successfully passing seaming tests. Master seamer shall have experience seaming a minimum of 3,000,000 square feet of geomembrane using same type of seaming apparatus to be used on this project.

3. Leak Location Contractor:

- d. 3 years of continuous experience in performing leak location surveys using electrical methods.
- e. Experience totaling a minimum of 2,000,000 square feet of geomembrane leak location surveys on some combination of at least 5 completed facilities.

1965 Section 02600 HDPE Geomembrane

NOT FOR CONSTRUCTION

Section 02600-2

f. Personnel performing survey qualified by experience with at least 2 years of geomembrane testing experience using the leak location survey electrical method.

B. Quality Assurance Program:

- Geomembrane Manufacturer/Installer shall conform with requirements of these Technical Specifications.
- The Owner or Contractor may engage and pay for the services of a Geosynthetic Quality Assurance Consultant and Laboratory to monitor geomembrane installation.

1.05 SUBMITTALS

- A. Prior to project start, submit the following to Geosynthetic Quality Assurance Consultant in accordance with Section 01300, Submittals:
 - 1. Raw Materials:
 - a. Name of Resin Supplier, location of supplier's production plant(s), resin brand name and product number.
 - b. Source and nature of plasticizers, fillers, carbon black and any other additives along with their percent addition to geomembrane material.
 - Test results documenting conformance with the "index properties" of GRI Test Method, GM 13.
 - Geomembrane Manufacturer's Certification:
 - a. Written certification that Geomembrane Manufacturer's Quality Control Plan was fully implemented during production of geomembrane material supplied for this project. (Submittal shall be made within 5 working days of delivery to site).
 - Geomembrane Installer's Seaming Personnel
 - a. Training completed by personnel.
 - b. Seaming experience for each personnel.
 - Geomembrane Manufacturer Production Information:
 - a. Corporate background information indicating compliance with qualification requirements.
 - b. Quality control plan for manufacturing.

1965 Section 02600 HDPE Geomembrane

- Copy of quality control certificates demonstrating compliance with the quality control plan for manufacturing and the test property requirements of GRI Test method, GM 13 (i.e. mill certificates).
- 5. Geomembrane Installer's Information:
 - Corporate background information indicating compliance with qualification requirements.
 - List of completed facilities, totaling 5,000,000 square feet minimum for which Geomembrane Installer has completed installation of a HDPE geomembrane. Include name and purpose of facility, location, date of installation, and quantity installed.
 - c. Resumes of personnel performing field seaming operation, along with pertinent experience information. Include documentation regarding which seamers are qualified to use thermal fusion welding apparatus.
 - d. Installation quality control plan.
- 6. Installation panel layout diagram identifying placement of geomembrane panels, seams, and any variance or additional details which deviate from Contract Drawings or Technical Specifications. Layout shall be drawn to scale and shall be adequate for use as a construction plan. Layout shall include dimensions and pertinent seam and anchorage details.
- Installation Sequence and Schedule shall be included as part of Construction Progress Schedule.
- 8. Description of seaming apparatus to be used.
- B. With bid, submit the following to Owner and/or Engineer in accordance with Section 01300, Submittals
 - 1. Leak Location Contractor's Work Plan:
 - a. Corporate background information indicating compliance with qualification requirements.
 - b. List of completed facilities, totaling 2,000,000 square feet minimum of geomembrane leak location surveys on some combination of at least 5 completed facilities. Include name and purpose of facility, location, date of survey, survey method, and quantity surveyed.
 - c. Resumes of personnel performing leak location survey, along with pertinent experience information.
 - Leak Location Contractor quality control plan including description of the proposed survey methods and procedures, and field calibration procedures.

1965 Section 02600 HDPE Geomembrane

- Leak Location Contractor's required site preparations to be completed to perform the proposed leak location survey, and estimated duration to complete the survey.
- f. An example of a final report (per ASTM D 7007) provided by the Leak Location Contractor following the completion of the survey.
- C. During installation, submit the following to the Geosynthetic Quality Assurance Consultant:
 - Daily records/logs prepared by Geomembrane Installer documenting work performed, personnel involved, general working conditions, and any problems encountered or anticipated on project. Submit on a weekly basis.
 - Copy of subgrade acceptance signed by Geomembrane Installer for areas to be covered with geomembrane each day.
- D. Within 10 days of geomembrane installation completion, submit the following to Geosynthetic Quality Assurance Consultant:
 - Geomembrane installation certification that Work was performed under Geomembrane Installer's approved quality control plan and in substantial compliance with Technical Specifications and Contract Drawings.
 - 2. As-built panel diagram identifying placement of geomembrane panels, seams, repairs, and destructive seam sample locations.
 - Copy of warranty for material (including factory seams) and installation covering both for a period of 2 years from the date of substantial completion.
- E. The Geosynthetic Quality Assurance Consultant will review and inspect HDPE geomembrane installation upon completion of all Work specified in this Section. Deficiencies noted shall be corrected at no additional cost to the Owner.
- F. The Geosynthetic Quality Assurance Consultant will provide written final acceptance of the geomembrane installation after completion of material placement above geomembrane. Written conditional geomembrane installation acceptance can be provided to the Contractor prior to completion of material placement above geomembrane when the following conditions are satisfied, if necessary, and requested by the Contractor:
 - 1. The entire geomembrane installation is completed or any pre-determined subsection if the project is phased.
 - 2. All installation quality assurance/control documentation has been completed and submitted to the Geosynthetic Quality Assurance Consultant or Owner.
 - Verification of the adequacy of all field seams, repairs and associated testing is complete.

1.06 DELIVERY, STORAGE, AND HANDLING

A. Transportation:

 Geomembrane rolls shall be transported, unloaded and handled at the job site in accordance with manufacturer recommendations. Damaged material may be rejected by the Geosynthetic Quality Assurance Consultant.

B. On-site Storage:

- Geomembrane rolls which have been delivered to job site shall be unloaded and stored in original, unopened packaging in a secure location, determined by Owner and/or Geosynthetic Quality Assurance Consultant.
- 2. Store geomembrane rolls to ensure adequate protection against exposure to the following:
 - a. Equipment;
 - Strong oxidizing chemicals, acids, or bases;
 - Flames, including welding sparks;
 - d. Temperatures in excess of 160 deg. F;
 - e. Dust;
 - f. Ultraviolet radiation (i.e. sunlight); and
 - g. Inclement weather.
- 3. Whenever possible, provide a 6-inch minimum air space between rolls.
- 4. Containers/rolls shall not be stacked.

C. On-Site Handling:

1. Handle rolls per Geomembrane Manufacturer's recommendations and as necessary to prevent damage.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. High Density Polyethylene (HDPE) White Textured Geomembrane.
 - HDPE geomembrane shall be white, textured, 60-mil product approved by the Engineer and/or Geosynthetic Quality Assurance Consultant.

1965 Section 02600 HDPE Geomembrane

- The Contractor shall submit, with the bid, written certification from the proposed Geomembrane Manufacturer that geomembrane products proposed in the bid satisfy the following requirements:
 - a. The proposed HDPE compound shall be comprised entirely of virgin materials. Compliance with this specification shall be documented in accordance with Geomembrane Manufacturer's quality control program and submitted to the Geosynthetic Quality Assurance Consultant with the written conformance certification.
 - b. The proposed Geomembrane Manufacturer shall certify that any plasticizers, fillers and additives incorporated into the manufacturing process for the proposed HDPE geomembrane have demonstrated acceptable performance on past projects.
 - The proposed geomembrane shall meet the requirements of Geosynthetic Research Institute's test method GM 13.
 - The nominal thickness of proposed geomembrane shall be 60 mil., or as approved by the Engineer and/or Geosynthetic Quality Assurance Consultant.
- Geomembrane sheets shall be visually consistent in appearance and shall contain
 no holes, blisters, undisbursed raw materials or other signs of contamination by
 foreign material. Geomembrane must have no striations, roughness or bubbles
 on the surface.

B. Seaming Apparatus

- Thermal fusion welding machines used for joining geomembrane surfaces may be either extrusion or hot wedge. These machines shall include sufficient temperature and rate-of-travel monitoring devices to allow continuous monitoring of operating conditions.
- 2. One spare, operable thermal fusion seaming device shall be maintained on site at all times.

C. Field Test Equipment

- 1. Field Tensiometer: the field tensiometer shall be calibrated within three months prior to project start date over the range of field test values.
- Air Channel Test Equipment: air channel test equipment shall consist of hoses, fittings, valves and pressure gauge(s) needed to deliver and monitor the pressure of compressed air through an approved pressure feed device.
- Air Compressor: the air compressor utilized for field testing shall be capable of producing and maintaining an operating pressure of at least 50 psi.
- Vacuum Box: the vacuum box shall consist of a vacuum gage, valve, and a
 gasket around the edge of the open bottom needed to apply vacuum to a surface.

1965 Section 02600 HDPE Geomembrane

2.02. CONFORMANCE TESTING REQUIREMENTS

A. Geomembrane shipped to site shall undergo conformance testing. Manufacturer's roll certificates may be used for conformance evaluation at the option of the Geosynthetic Assurance Consultant. Nonconforming material shall either be retested at the direction of the Geosynthetic Quality Assurance Consultant or removed from site and replaced at Contractor's expense.

B. Conformance Test Methods

- Samples will be located and collected by the Geosynthetic Quality Assurance
 Consultant at a rate of one sample per 100,000 square feet of geomembrane
 delivered to site.
- One sample will be obtained from each geomembrane production batch delivered to the site.
- 3 Samples shall be cut by Geomembrane Installer and be at least 45 square feet in size.
- Samples shall be tested in accordance with Table 1 (Smooth) or Table 2 (Textured) specified in GRI Test Method GM13.
- Geomembrane thickness shall be measured a minimum of three times per panel during deployment to verify conformance with GRI Test Method GM13.

C. Role of Testing Laboratories

- The Geosynthetic Quality Assurance Consultant will be responsible for acquiring samples of the geomembrane for conformance testing. The Owner or Geosynthetic Quality Assurance Consultant will retain an independent, third party laboratory to perform conformance testing on samples of geomembrane.
- Retesting of geomembrane panels by the Geomembrane Installer because of failure to meet any of the conformance specifications can only be authorized by the Geosynthetic Quality Assurance Consultant.
- The Geomembrane Manufacturer and/or Geomembrane Installer may perform
 independent tests in accordance with methods and procedures specified in GRI
 GM 13. Results shall not be substituted for quality assurance testing described
 herein.
- D. Procedures for Determining Conformance Test Failures

- 1. If conformance test results fail to meet specifications, the roll and/or batch may be retested using specimens from either the original roll sample or from another sample collected by the Geosynthetic Quality Assurance Consultant. Two additional tests (retests) shall be performed for each failed test procedure. Each retest shall consist of multiple specimen tests if multiple specimens are specified in the test procedure. If the results of both retests meet specifications, the roll and batch will be considered to have passed conformance testing.
- 2. Failure of any retest shall be cause for rejection of the entire roll or batch depending on the type of failing test. The Geosynthetic Quality Assurance Consultant reserves the right to collect samples from other rolls of a particular batch for further conformance testing. The Geosynthetic Quality Assurance Consultant may choose to accept only a portion of the batch on the basis of the results of conformance testing of samples collected from other rolls.
- 3. If retesting does not result in conformance with the specifications as defined in preceding paragraph, or if there are any other nonconformities with the material specifications, the Contractor shall remove the rolls from use in the project. The Contractor shall also be responsible for removal of rejected geomembrane from the site and replacement with acceptable geomembrane at no additional cost to the Owner.

PART 3 - EXECUTION

3.01 PRE-CONSTRUCTION MEETING

- A. A Pre-Construction Meeting shall be held at the site to discuss and plan the details of geomembrane installation. This meeting shall be attended by the Geomembrane Installer, Owner, Engineer and the Contractor.
- B. The following topics relating to geomembrane installation shall be addressed:
 - 1. Responsibilities of each party.
 - 2. Lines of authority and communication.
 - 3. Methods for documenting, reporting and distributing documents and reports.
 - 4. Procedures for packaging and storing archive samples.
 - Review of the schedule for all installation and quality assurance testing, including third-party testing turnaround times.
 - Review of panel layout, access and numbering systems for panels and seams including details for marking on the HDPE geomembrane.
 - Procedures and responsibilities for preparation and submittal of as-built drawings.

1965 Section 02600 HDPE Geomembrane

- Temperature and weather limitations, installation procedures for adverse weather conditions and defining acceptable subgrade or ambient moisture and temperature conditions for working during liner installation.
- Subgrade conditions, dewatering responsibilities and subgrade maintenance plan.
- 10. Deployment techniques including allowable subgrade for geomembrane.
- 11. Procedures for covering of the geomembrane to prevent damage.
- 12. Plan for minimizing wrinkles in the geomembrane.
- 13. Measurement and payment schedules.
- 14. Site health and safety procedures/protocols.

3.02 SUBGRADE PREPARATION

- Contractor shall prepare a subgrade surface in accordance with Section 02300, Earthwork.
- B. The Contractor shall not excavate more than the amount of anchor trench required for one day of geosynthetics deployment, unless otherwise specified by the Geosynthetic Quality Assurance Consultant. Rounded corners shall be provided in the trenches where the geosynthetics enter the trench to allow them to be uniformly supported by the subgrade and to avoid sharp bends. The geosynthetics shall not be supported by loose soils in anchor trenches.
- C. The Geomembrane Installer shall visually inspect the subgrade immediately prior to geomembrane deployment. Inspection shall verify that there are no potentially harmful foreign objects present, such as sharp rocks and other deleterious debris. Any foreign objects encountered shall be removed by Geomembrane Installer or Contractor. All subgrade damaged by construction equipment and deemed unsuitable for geomembrane deployment shall be repaired prior to geomembrane deployment. All repairs shall be approved by the Geosynthetic Quality Assurance Consultant and Geomembrane Installer. The responsibility for preparation, repairs, and maintenance of the subgrade shall be defined in the preconstruction meeting. The Geomembrane Installer shall provide the Geosynthetic Quality Assurance Consultant with written acceptance of subgrade surface over which geomembrane is deployed (Part 1.05C) for each day of deployment.

3.03 GEOMEMBRANE DEPLOYMENT

A. Geomembrane shall not be deployed until all applicable certifications/quality control certificates listed in Subsection 1.05 of this section and conformance testing listed in Subsection 2.02 of this section are submitted and approved by the Geosynthetic Quality Assurance Consultant. Any geomembrane deployed prior to approval by the Geosynthetic Quality Assurance Consultant shall be at the sole risk of the Geomembrane Installer and/or Contractor. If material installed prior to approval by the Geosynthetic Quality Assurance Consultant does not meet the requirements of this specification, it shall be removed from the site at no additional cost to the Owner.

1965 Section 02600 HDPE Geomembrane

- B. Geomembrane will be deployed according to submitted panel layout drawing as approved by the Geosynthetic Quality Assurance Consultant. The Geosynthetic Quality Assurance Consultant is to be notified of and approve any revisions or modifications to the approved panel layout drawing prior to deploying geomembrane in the area of review.
- C. Adequate temporary anchoring (sand bags, tires, etc.) that will not damage the geomembrane shall be placed on a deployed panel to prevent uplift by wind.
- D. Geomembrane shall not be deployed if:
 - 1. Ambient temperatures are below 41 degrees F (5 degrees C) or above 104 degrees F (40 degrees C) measured six inches above geomembrane surface unless approved by the Geosynthetic Quality Assurance Consultant.
 - 2. Precipitation is expected or in the presence of excessive moisture or ponded water on the subgrade surface.
 - 3. Winds are excessive as determined by Geomembrane Installer in agreement with the Geosynthetic Quality Assurance Consultant.
 - 4. The Geosynthetic Quality Assurance Consultant will have the authority to suspend work during such conditions.
- E. The Geomembrane Installer shall be responsible for conformance with the following requirements:
 - Equipment utilized for installation/quality assurance testing does not damage geomembrane. Such equipment shall have rubber tires and a ground pressure not exceeding 5 psi or total weight exceeding 750 lbs. Only equipment necessary for installation and quality assurance testing is allowed on the deployed geomembrane.
 - 2. Personnel working on geomembrane do not damage geomembrane (activities such as smoking or wearing damaging clothing shall not be allowed).
 - Method of deployment does not damage geomembrane.
 - 4. Method of deployment minimizes wrinkles.
 - 5. Temporary loading or anchoring does not damage geomembrane.
 - 6. Direct contact with geomembrane is minimized.
- F. No vehicles shall be allowed on deployed geomembrane under any circumstances.

3.04 FIELD SEAMS

- A. Seam Layout
 - 1. In general, seams shall be oriented parallel to the line of the maximum slope. In corners and at other odd-shaped geometric intersections, number of seams should

1965 Section 02600 HDPE Geomembrane

be minimized. If at all possible, seams shall not be located at low points in the subgrade unless geometry requires seaming to be done at these locations.

2. A seam numbering system compatible with the panel numbering system shall be agreed upon at the Pre-Construction Meeting.

B. Seaming Processes/Equipment

- Approved processes for field seaming (panel to panel) are extrusion or hot wedge
 fusion-type seam methods. No other processes can be used without prior written
 authorization from the Geosynthetic Quality Assurance Consultant. Only
 equipment which has been specifically approved by make and model shall be
 used, if applicable.
- 4. The Geomembrane Installer will meet the following requirements regarding use, availability, and cleaning of welding equipment at job site:
 - Intersecting hot wedge seams shall be patched using extrusion welding process.
 - b. Electric generator for equipment shall be placed on a smooth base such that no damage occurs to geomembrane. A smooth insulating plate or fabric shall be placed beneath hot equipment after usage.
- The Geomembrane Installer shall keep records for performance and testing of all seams.

C. Seaming Requirements/Procedures

- 1. Weather Conditions Range of weather conditions under which geomembrane seaming can be performed are as follows:
 - a. Unless otherwise authorized in writing by Geosynthetic Quality Assurance Consultant, no seaming shall be attempted or performed at an ambient temperature below 41 degrees F (5 degrees C) or above 104 degrees F (40 degrees C).
 - b. Between ambient temperatures of 32 degrees F (0 degrees C) and 41 degrees F (5 degrees C), seaming shall be performed only if geomembrane is preheated by either sun or a hot air device, provided there is no excessive ambient cooling resulting from high winds. Prequalification seams shall be produced under identical conditions.
 - Above 41 degrees F (5 degrees C), no preheating of geomembrane will be required.
 - d. Geomembrane shall be dry and protected from wind.
 - e. Seaming shall not be performed during any precipitation event.

- f. Seaming shall not be performed in areas where ponded water has collected below surface of geomembrane.
- 2. If the Geomembrane Installer chooses to use methods which may allow seaming at ambient temperatures below 41 degrees F or above 104 degrees F, the Geomembrane Installer shall demonstrate and submit certification to Geosynthetic Quality Assurance Consultant that methods and techniques used to perform seaming produce seams that are equivalent to seams produced at temperatures above 41 degrees F and below 104 degrees F. The Geosynthetic Quality Assurance Consultant may deny approval for use of the proposed technique regardless of demonstration results.
- 3. Overlapping Geomembrane panels shall have finished overlap as follows:
 - a. Minimum of 6 inches for thermal fusion welding.
 - b. Insufficient overlap will be considered a failed seam.
- 4. Pre-qualification tests for geomembrane fusion welding shall be conducted by a minimum of 2 pre-qualification seams conducted per day per welding machine by each seaming technician performing welding with that machine. At least one test shall be performed at the start of each work day, with tests at intervals of no greater than 5 hours and additional pre-qualification tests following work interruptions, weather changes, changes to machine settings, or as directed by the Geosynthetic Quality Assurance Consultant. Pre-qualification seams shall be made under the same conditions as the actual seams.
 - a. Pre-qualification seam samples shall be 5 feet long by 1-foot wide (minimum) after seaming, with seam centered along its length. Each pre-qualification seam shall be labeled with the date, geomembrane temperature, seaming unit identifier, seam number or test location, technician performing the test seam and description of testing results.
 - b. Seam overlap shall be in accordance with Subsection 3.04(C)(3).
 - c. Pre-qualification seams shall be inspected for proper squeeze-out, footprint pressure, and general appearance.
 - d. Four specimens, each 1-inch in length, shall be cut from opposite ends of the pre-qualification seam sample by the Geomembrane Installer. The remainder of pre-qualification seam shall be retained by the Geosynthetic Quality Assurance Consultant and may be submitted for laboratory testing.
 - e. The Geomembrane Installer shall complete two shear tests and two peel tests in accordance with GRI GM 19.
 - f. Pre-qualification seams failed by inspection or testing may be retested at request of the Geomembrane Installer. If the second pre-qualification seam fails, then the seaming apparatus or seaming technique shall be

disqualified from use until two consecutive, satisfactory pre-qualification seams are obtained.

5. Seam Preparation

- a. Prior to seaming, seam area shall be clean and free of moisture, dust, dirt, debris of any kind, and foreign material.
- b. Seams shall be aligned so as to minimize number of wrinkles and fishmouths.

6. General Seaming Procedures

- a. Fishmouths or wrinkles at seam overlaps shall be cut along ridge of the wrinkle to achieve a flat overlap. Cut fishmouths or wrinkles shall be repaired, and/or patched in accordance with Part 3.08.
- b. Seaming shall extend to the outside edge of geomembrane panels including material placed in anchor trenches.
- The intersecting thermal fusion seams shall be patched using the extrusion welding process.

3.05 NON-DESTRUCTIVE TESTING

- A. Each field seam shall be non-destructively tested over its entire length by the Installer. Testing shall be conducted as field seaming progresses, not at completion of all seams, unless specifically agreed to by the Geosynthetic Quality Assurance Consultant in writing.
- B. Vacuum Testing shall be performed in accordance with ASTM D5641.
- C. Air Pressure Testing shall be performed in accordance with ASTM D5820, and GRI GM 6, Pressurized Air Channel Test for Dual Seamed Geomembranes.
- D. Each seam tested non-destructively shall be marked with the date of the test, name of the testing technician, length of the seam, test method and results. The same shall also be recorded by the Geosynthetic Quality Assurance Consultant on the appropriate CQA documentation.
- E. Non-Destructive Seam Test Failures
 - Seams failing non-destructive testing shall be repaired by the Geomembrane
 Installer according to Part 3.08. Seams shall be non-destructively retested. If the
 seam defect cannot be located, the entire section of seam affected shall be
 repaired and retested.

3.06 DESTRUCTIVE TESTING

- A. The Owner shall have the option to destructively test geomembrane panel seams completed in the field. Destructive seam testing shall be performed by the Geomembrane Installer under the observation of the Geosynthetic Quality Assurance Consultant.
- B. Sampling Procedure
 - 1. For each sample location, the Geosynthetic Installer will:
 - a. Assign a sample number and mark the sample accordingly.
 - b. Record the sample location on the as-built layout drawing.
 - c. By sample number, record reason for collecting sample (e.g., as part of statistical testing program, suspicious seam, retest, etc.).
 - d. Record pertinent information, including date, time, seam number, number of seaming unit, and name of seamer, on the seam sample.
 - Each destructive sample shall be at least 12 inches wide (at least 6 inches on each side of seam) by 54 inches long. Samples will be cut by the Geomembrane Installer and distributed as follows:
 - a. A 12-inch by 12-inch portion shall be cut and tested in accordance with Subsection 3.06(C) by the Geomembrane Installer.
 - A 12-inch by 12-inch portion shall be cut and retained by the Geomembrane Installer. The Geomembrane Installer may elect to omit this requirement.
 - A 12-inch by 12-inch portion shall be cut and retained by the
 Geosynthetic Quality Assurance Consultant as an archive sample.
 - d. A 12-inch by 18-inch portion shall be submitted by the Geosynthetic Quality Assurance Consultant for laboratory testing as described in Part 3.06(D).
 - 3. Ten specimens, each 1 inch wide by 12 inches long with seam centered perpendicular to width, shall be collected and field tested by the Geomembrane Installer prior to shipping the sample to the laboratory. If all samples pass field tensiometer test described in Part 3.06(C), then the laboratory sample shall be submitted for testing by the Geosynthetic Quality Assurance Consultant.
 - Holes cut into geomembrane resulting from destructive seam sampling shall be immediately repaired by Geomembrane Installer in accordance with repair procedures described in Part 3.08.

1965 Section 02600 HDPE Geomembrane

The state of the s

C. Field Test Methods

- Ten 1-inch-wide samples described above under Part 3.06(B)(3) shall be field tested for peel (5 samples) and shear (5 samples) in accordance with GRI GM 19.
- 2. One seam sample shall be field tested for peel and shear at the end of each continuous field seam 100 feet or greater in length.
- Testing shall be performed in accordance with ASTM D6392 using a field tensiometer or equivalent device to qualitatively and quantitatively determine mode of failure.
- Seam shall be considered passing if failure in both peel and shear meet criteria listed in GRI GM 19.
- 5. The procedures specified in Subsection 3.06(D) shall be implemented when sample passes field tensiometer test.

D. Laboratory Test Methods

- Laboratory testing of seam samples shall be conducted by the Geosynthetic
 Quality Assurance Laboratory under contract with the Geosynthetic Quality
 Assurance Consultant or Owner. Five specimens shall be tested in shear and five
 in peel.
- Laboratory testing shall be conducted in accordance with GRI GM 19.
- For both seam shear and peel tension tests, an indication will be given for each specimen tested which defines locus of failure.
- 4. For shear tests, the following values, along with the mean and standard deviation where appropriate, will be reported for each specimen tested:
 - a. Maximum tension in pounds per square inch.
 - b. Elongation at break (up to a tested maximum of 100 percent).
 - Locus of failure using ASTM D6392 designations.
- 5. For peel tests, the following values, along with the mean and standard deviation where appropriate, will be reported for each specimen tested:
 - a. Maximum tension in pounds per square inch.
 - b. Seam separation (expressed as percent of original seam area).

- c. Locus of failure.
- Retesting of seams due to nonconformance with specifications may be performed at the discretion of the Geosynthetic Quality Assurance Consultant.

E. Destructive Seam Test Failure

- Shear and peel test results derived from testing described in Parts 3.06(C) and
 3.06(D) shall comply with GRI GM 19 for seam to be considered acceptable.
- 2. The Geomembrane Installer has two options in determining the repair boundary whenever a seam has failed destructive testing:
 - The seam can be reconstructed between the two previously tested and passed destructive sample locations; or,
 - b. The Geomembrane Installer can trace the welding path to an intermediate location at least ten feet from point of failed test in each direction and obtain destructive test samples collected from these locations. If destructive tests on these samples are acceptable, then the seam shall be reconstructed between the intermediate locations. If either sample fails, the process may be repeated until an acceptable seam test has been performed on both sides of the original failed sample. If a passing sample is not realized on one (or both) side of the original failed sample, then seam repair must extend to the end(s) of the seam. Retesting of seams according to this procedure shall utilize the sampling methodology described in Part 3.06(B). The Owner reserves the right to terminate this process, at the discretion of the Geosynthetic Quality Assurance Consultant, after the second retesting. An additional sample taken from the reconstructed zone must pass destructive seam testing if destructive sample failure(s) causes reconstruction.
- The Geosynthetic Quality Assurance Consultant shall be responsible for documenting all actions taken in repairing seams. The Geomembrane Installer will be responsible for keeping the Geosynthetic Quality Assurance Consultant informed of seaming progress.
- Additional fees for destructive seam test failures shall be assessed to the Contractor and deducted from payment. This fee shall be assessed only if the failing sample is a laboratory sample.

3.07 ELECTRONIC LEAK LOCATION SURVEY

- A. The Owner shall have the option to conduct an electronic leak location survey. Leak location survey shall be performed by the Leak Location Contractor under the observation of the Geosynthetic Quality Assurance Consultant.
- B. Leak Location Contractor shall identify actions required by Contractor to prepare the site for the leak location survey.
- C. Contractor shall ensure that the layers above and below the geomembrane contains sufficient moisture to conduct a leak location survey. Typically, a moisture content of earth materials of 1% to 2% by weight is sufficient to conduct the survey. If the moisture content of layers above and/or below the geomembrane is not sufficient per the requirements of the Leak Location Contractor, Contractor shall add moisture to the layers, as required.
- D. Contractor shall provide electrical isolation of the metal marker posts, batten bars, and concrete structures, as requested by Leak Location Contractor.
- E. Leak Location Contractor shall inspect the site prior to commencing the survey to ensure all site preparations are completed and the site conditions are appropriate for conducting the leak location survey.
- F. Any discrepancy in the required site preparation detailed in the Leak Location Contractor's Work Plan or site conditions shall be reported to the Contractor for corrective or appropriate action.
- G. After the final layer is placed above the geomembrane, conduct a leak location survey on the final layer material using the procedures for surveys with earth materials covering the Geomembrane as described in ASTM D 7007.
- H. A leak detection sensitivity test using an artificial leak shall be conducted on the geomembrane for each set of equipment used before the equipment is used on for the leak location survey, as described in ASTM D 7007 to determine the detection distance for the survey.
- I. The leak location survey shall be taken on survey lines or on a grid spaced no farther apart than twice the leak detection distance as determined in the leak detection sensitivity test.
- J. The Leak Location Contractor shall inform the Owner and/or Engineer and mark the locations of all identified or indicated leaks with a flag or spray paint. The Geomembrane Installer shall repair the defect/hole as detailed in Part 3.08 of this Section.

3.08 DEFECTS AND REPAIRS

A. The geomembrane shall be examined by the Geomembrane Installer and the Engineer for defects, holes, blisters, undispersed raw materials, and any signs of contamination by foreign matter. The geomembrane surface shall be swept and/or washed by the Geomembrane Installer if the amount of dust or mud inhibits examination. The

1965 Section 02600 HDPE Geomembrane

Contractor shall provide a water truck, an operator, clean water and hoses as reasonably necessary to assist the Geomembrane Installer in this activity.

- B. Portions of geomembrane exhibiting flaws, or failing a non-destructive or destructive (if conducted) test, shall be repaired or replaced by the Geomembrane Installer. Repair procedures available include:
 - 1. Patching used to repair large holes, tears, undispersed raw materials, contamination by foreign matter, holes resulting from destructive sampling (if conducted), and locations where seam overlap is insufficient;
 - 2. Capping used to repair large lengths of failed seams; and
 - 3. Additional Procedures used upon recommendation of the Geomembrane Installer if agreed to by the Engineer.
- C. Patches or caps.
 - 1. Extend patch or cap 6 inches (minimum) beyond the edge of the defect.
 - 2. Round corners of patch and/or cap (suggest 3-inch radius).
 - 3. Repair procedures, equipment, materials, and techniques will be approved by the Geosynthetic Quality Assurance Consultant prior to repair.
 - Geomembrane below large caps shall be appropriately cut to avoid water or gas collection between two sheets.
- D. The Geomembrane Installer shall mark on the geomembrane (using a non-puncturing writing utensil), repair date, time, and personnel involved.
- E. Each repair shall be non-destructively tested in accordance with Part 3.05. Large caps may require destructive test sampling in accordance with Part 3.06 at the discretion of the Geosynthetic Quality Assurance Consultant.
- F. Repairs which fail testing shall be redone and retested until a passing result is obtained.

 The Geomembrane Installer will perform non-destructive testing on repairs and will document retesting of repairs.
- G. The Geosynthetic Quality Assurance Consultant will document repairs, repair testing, and retesting results.
- H. The Geomembrane Installer shall cut and seam wrinkles which may adversely affect long-term integrity of the geomembrane, hinder subsequent construction of overlying layers, or impede drainage off of the geomembrane after it is covered by soil. Seaming shall be done in accordance with procedures described in Parts 3.04(B) and 3.04(C), and it shall be subject to test provisions of Parts 3.05 (non-destructive testing) and 3.06 (destructive testing if conducted).

1965 Section 02600 HDPE Geomembrane

3.09 PROTRUSIONS AND CONNECTIONS TO GEOMEMBRANE

- A. If required, the Geomembrane Installer shall install geomembrane around utility poles, guy wires, and other structures according to the Contract Drawings and the following requirements:
 - 1. Use minimum 1-ft long geomembrane pipe boots and steel clamps to seal the geomembrane around pole or structure.
 - 2. Use standard welding procedures to seam the geomembrane boot to the geomembrane.
 - Seaming performed on and around penetrations, and other appurtenances shall be non-destructively tested using the vacuum testing method.

3.10 SURVEY DOCUMENTATION

A. The Geomembrane Installer shall survey the completed geomembrane prior to covering and provide the Geosynthetic Quality Assurance Consultant with 24-hour notification of survey. The Contractor shall document the location of all seams (panel corners acceptable), destructive test samples (if conducted) and repairs. The Contractor shall provide survey data to the Geosynthetic Quality Assurance Consultant within two working day of survey completion.

3.11 DAILY FIELD INSTALLATION REPORTS

- A. At the beginning of each day, the Geomembrane Installer shall provide the Geosynthetic Quality Assurance Consultant with a report for all work completed the previous day.
- B. The Daily Field Installation Report shall include the following:
 - 1. The total amount and location of geomembrane placed.
 - 2. The total length and location of seams completed, technician name and welding unit numbers.
 - 3. A drawing or sketch depicting the geomembrane installed the previous day including the panel number, seam number and locations of non-destructive and destructive testing (if conducted).
 - 4. Results of pre-qualification test seams, if available.
 - 5. Results of non-destructive testing.
- C. Destructive test results (if conducted) shall be reported within 48 hours or prior to covering the geomembrane, whichever is practical.

3.12 MATERIAL ABOVE GEOMEMBRANE

- A. The Geosynthetic Quality Assurance Consultant and Geomembrane Installer shall verify the area of geomembrane completion prior to placement of material over the geomembrane.
- B. Soils Apply following general criteria for covering of the geomembrane:
 - Do not place soils on the geomembrane at an ambient temperature below 32 degrees F, (0 degrees C) nor above 104 degrees F (40 degrees C), unless otherwise specified.
 - 2. Do not drive equipment used for placing soil directly on the geomembrane.
 - A minimum thickness of 1 foot of soil is specified between a low ground pressure dozer (maximum contact pressure of 5 lb/sq. inch) and the geomembrane.
 - 4. A minimum thickness of 2 feet of soil is required between rubber-tired vehicles and the geomembrane.
 - 5. Do not compact soils placed directly on geomembrane.
 - Damage to the geomembrane resulting from placement of cover soils shall be repaired in accordance with Part 3.08 by the Geomembrane Installer at the Contractor's expense.
 - 7. Do not push soil downslope. Soil shall be placed over the geomembrane starting from base of the slope, up to top of the slope.

END OF SECTION

1965 Section 02600 HDPE Geomembrane

1

SHEETS

south 2 From the A

SHEETS

