



February 1, 2022

Illinois Environmental Protection Agency
DWPC – Permits MC #15
Attn: Part 845 Coal Combustion Residual Rule Submittal
1021 North Grand Avenue East
Springfield, IL 62794-9276

Hand-Delivered

Re: City Water, Light and Power
Closure Construction Permit Application

Dear Correspondent:

On behalf of City Water, Light and Power, submitted herein is a Closure Construction application for the Lakeside Ash Pond and Dallman Ash Pond pursuant to Ill. Adm. Code 845.750. The CCR 1, CCR 2CC, and CCR 2CA forms are provided in Attachment A of the application. A digital copy of the application was uploaded to the following address:
<https://filet.illinois.gov/filet/PIMupload.asp>.

If you have any questions or require further information, please contact P.J. Becker at (217) 757-8610, extension 1110. Thank you.

Sincerely,

Brad Hunsberger, LPG
Vice President

w/attachments

cc: P.J. Becker – CWLP (hard copy and electronic file)
Deborah Williams – CWLP (electronic file)
Eric Staley – CWLP (electronic file)
Tabitha Bernhardt – Illinois EPA (electronic file)
Paul Van Metre - Andrews Engineering (cover letter only)

City Water, Light & Power

CCR Impoundments – Lakeside and Dallman Ash Ponds

Springfield, Sangamon County, Illinois

Closure Construction Permit Application

February 2022



Submitted to:

Illinois Environmental Protection Agency
Bureau of Water
1021 North Grand Avenue East
Springfield, Illinois



Prepared for:

City Water, Light & Power
3100 Stevenson Drive
Springfield, Illinois 62703



3300 Ginger Creek Drive, Springfield, IL 62711 | 217.787.2334

ILLINOIS | MISSOURI | INDIANA

TABLE OF CONTENTS

1. INTRODUCTION	1
2. DESIGN AND CONSTRUCTION PLANS	1
2.1 Physical and Engineering Properties of the Foundation and Abutment Materials on which the CCR Surface Impoundment is Constructed.....	1
2.2 Type, Size, Range, and Physical and Engineering Properties of the Materials Used in Constructing Each Zone or Stage of the CCR Surface Impoundment.....	2
2.3 Method of Site Preparation and Construction of Each Zone of Each Impoundment ..	3
2.4 Dates of Construction of Each Successive Stage of Construction of the CCR Surface Impoundment.....	4
2.5 Drawing Satisfying the Requirements of 35 IAC 845.220(a)(1)(F).....	5
2.6 Type, Purpose, and Location of Existing Instrumentation.....	5
2.7 Area Capacity Curves for the CCR Impoundment.....	5
2.8 Spillway and Diversion Design Features, Capacities and Calculations Used in their Determination	5
2.9 Construction Specifications and Provisions for Surveillance, Maintenance, and Repair of the CCR Surface Impoundment.....	6
2.10 Record or Knowledge of Structural Instability of the CCR Surface Impoundment	8
3. NARATIVE DESCRIPTION OF THE FACILITY.....	8
3.1 Types of CCR and Chemical Analyses of CCR Placed in the Surface Impoundments	8
3.2 Maximum Capacity of Each Surface Impoundment.....	8
3.3 Rate of Waste Streams Entering Impoundments	9
3.4 Length of Time Impoundments will Receive Waste.....	9
3.5 On-Site Transportation used During Operation of the Impoundments.....	9
4. MAPS	9
4.1 Site Location Map.....	9
4.2 Site Plan Map	9
5. PROPOSED CONSTRUCTION INFORMATION	10
5.1 Description of Proposed Construction.....	10
5.2 Plans and Specifications.....	10
5.3 Signature and Seal of Qualified Professional Engineer.....	10
5.4 Public Notification and Meetings Certification	10
5.5 Summary of Issues Raised by the Public During the Notification and Public Meetings	10
5.6 Summary of Revisions, Determinations, or Other Considerations Made in Response to Issues Raised by the Public During the Notification and Public Meetings.....	10
5.7 List of Interested Persons in Attendance who Would Like Added to the Agency's listserv for the Facility	11
5.8 Certification of Contractors/Subcontractors for Erosion Control Training.....	11
5.9 Certification of Contractors/Subcontractors for Erosion Control Training.....	11
6. GROUNDWATER MONITORING PROGRAM.....	11
6.1 Hydrogeologic Site Investigation.....	11
6.2 Design and Construction Plans of the Groundwater Monitoring System	12
6.3 Groundwater Sampling and Analysis Plan	12

7. CLOSURE12

7.1 Final Closure Plan12

7.2 Proposed Closure Schedule12

7.3 Post-Closure Care Plan12

8. GROUNDWATER MODELING.....12

8.1 Results of Groundwater Contaminant Transport Model12

8.2 Modeling Input and Assumptions12

8.3 Description of Fate and Transport of Contaminants13

8.4 Capture Zone Modeling13

8.5 Model License and Software.....13

9. CORRECTIVE ACTION.....13

9.1 Drawing Satisfying the Requirements of 35 IAC 845.220(a)(1)(F).....13

9.2 Type, Purpose, and Location of Existing Instrumentation.....13

9.3 Area Capacity Curves for the CCR Impoundment.....13

9.4 Spillway and Diversion Design Features, Capacities and Calculations Used in their Determination13

9.5 Construction Specifications and Provisions for Surveillance, Maintenance, and Repair of the CCR Surface Impoundment.....13

9.6 Physical and Engineering Properties of the Foundation and Abutment Materials on which the CCR Surface Impoundment is Constructed.....13

9.7 Type, Size, Range, and Physical and Engineering Properties of the Materials Used in Constructing Each Zone or Stage of the CCR Surface Impoundment14

9.8 Method of Site Preparation and Construction of Each Zone of Each Impoundment .14

9.9 Dates of Construction of Each Successive Stage of Construction of the CCR Surface Impoundment.....14

10. NARATIVE DESCRIPTION OF FACILITY.....14

10.1 Types of CCR and Chemical Analyses of CCR Placed in the Surface Impoundments 14

10.2 Maximum Capacity of Each Surface Impoundment.....14

10.3 Rate of Waste Streams Entering Impoundments14

10.4 Length of Time Impoundments will Receive Waste14

10.5 On-Site Transportation used During Operation of the Impoundments14

11. MAPS14

11.1 Site Location Map14

11.2 Site Plan Map14

12. PROPOSED CONSTRUCTION INFORMATION15

12.1 Description of Proposed Construction15

12.2 Plans and Specifications.....15

12.3 Signature and Seal of Qualified Professional Engineer15

12.4 Public Notification and Meetings Certification15

12.5 Summary of Issues Raised by the Public During the Notification and Public Meetings 15

12.6 Summary of Revisions, Determinations, or Other Considerations Made in Response to Issues Raised by the Public During the Notification and Public Meetings.....15

12.7 List of Interested Persons in Attendance who Would Like Added to the Agency's listserv for the Facility15

12.8 Certification of Contractors/Subcontractors for Erosion Control Training.....15

12.9 Certification of Contractors/Subcontractors for Erosion Control Training..... 15

13. GROUNDWATER MONITORING PROGRAM.....15

13.1 Hydrogeologic Site Investigation..... 15

13.2 Design and Construction Plans of the Groundwater Monitoring System 16

13.3 Groundwater Sampling and Analysis Plan 16

14. CORRECTIVE ACTION.....16

14.1 Corrective Action Plan 16

14.2 Corrective Action Groundwater Monitoring Program 16

14.3 Interim Measures 16

15. GROUNDWATER MODELING.....16

15.1 Results of Groundwater Contaminant Transport Model 16

15.2 Modeling Input and Assumptions..... 16

15.3 Description of Fate and Transport of Contaminants 16

15.4 Capture Zone Modeling 17

15.5 Model License and Software..... 17

FIGURES

Figure 1 – Site Location

Figure 2 – Site Details

ATTACHMENTS

Attachment 1 – Form CCR1, Form CCR 2CC and Form CCR 2CA

Attachment 2 – 1987 Engineering Report

Attachment 3 – Safety Factor Assessment

Attachment 4 – 2016 History of Construction Report

Attachment 5 – Analytical Report for CCR Surface Impoundments

Attachment 6 – Site Location Map

Attachment 7 – Site Plan Map

Attachment 8 – Plans and Specifications/Construction Quality Assurance Plan

Attachment 9 – Signature and Seal of Qualified Engineer

Attachment 10 – Completion of Public Notice and Public Meetings Certification

Attachment 11 – Closure Alternatives Assessment and Assessment of Corrective Action

Attachment 12 – Hydrogeologic Report, Groundwater Monitoring Program and Statistical Procedures

Attachment 13 – Final Closure Plan

Attachment 14 – Post-Closure Care Plan