An EDISON INTERNATIONAL® Company

Maria Race Environmental Program Director

WALLEST TO SERVE AND ADDRESS OF THE PARTY OF

June 30, 2010

Mr. Jaime Rabins
Illinois Environmental Protection Agency
Division of Water Pollution Control
1021 North Grand Avenue East
Springfield, Illinois 62702

RE: Application for Permit or Construction Approval
Bypass Basin Liner Replacement
Midwest Generation Powerton Power Station - 13082 East Manito Road, Pekin, IL
NPDES Permit No. IL0002232

Dear Mr. Rabins:

Midwest Generation, LLC (MWG) is requesting a construction permit for liner replacement in the Bypass Basin at the Powerton Generating Station. This activity is part of MWG's routine maintenance program for the facility; no significant modifications will be made to the basin's operation or treatment process. Please find enclosed a copy of the Application for Permit or Construction Approval WPC-PS-1 and supporting documents.

The following information is attached:

A site location map is included in the "Figure" tab;

A plan view of existing conditions, liner replacement plan, cross section and details drawings are included in the "Sheets" tab;

Form WPC-PS-1 "Application for Permit or Construction Approval", and Schedules G "Sludge Disposal & Utilization", J "Industrial Treatment Works Construction or Pretreatment Works", and N "Waste Characteristics" are provided in Appendix A;

Representative photographs of the Bypass Basin are provided in Appendix B; and

Specification Section 02600 for installation of high-density polyethylene (HDPE) geomembrane liner is provided in Appendix C.

FACILITY DESCRIPTION


The Bypass Basin is for settling of solid/coal ash waste associated with electrical power generation when the Primary Ash Settling Basin is temporarily out-of-service for maintenance. Currently, the basin is lined with chlorosulfonated polyethylene (Hypalon®) liner on the side slopes, and a 12-inch thick layer of Poz-o-pac¹ at the base. The basin only operates during maintenance of the Primary Ash Settling Basin, which generally occurs for a few weeks every 6 years. The total depth of the basin is 8 feet with a working volume of approximately 1.7 million gallons and a design maximum flow (DMF) of 32.4 million gallons per day (MGD). Typically, the basin freeboard is 2 feet during operation. Photographs of the current condition of the basin are provided in Appendix B.

235 Remington Blvd.

Suite A

Bolingbrook, Il 60440 Tel: 630 771 7862

Fax: 312 788 5526 mracc@mwgen.com



¹ A stabilized subgrade that is comprised of lime, fly ash and aggregate. Compressive strength could be between 500 to 1,000 psi.

Mr. Jaime Rabins, Div. of Water Pollution Control, IEPA June 30, 2010 Page 2

PROJECT DESCRIPTION

The Bypass Basin at the Powerton Power Station will undergo a liner replacement by the addition of a 60 mil HDPE geomembrane liner. Liner replacement activities for the Bypass Basin are anticipated to occur Fall 2010, following scheduled dredging activities (dewatering followed by dry excavation). This schedule may change based upon plant operation needs. Liner replacement activities will include:

- Subgrade preparation for HDPE geomembrane liner (Sheet C020), including removal of the existing Poz-o-Pac layer (12-inches thick) and 6-inches of the Poz-o-Pac subgrade material at the base of the basin to accommodate a warning layer above the replacement liner, as described below.
 - MWG, depending on budget constraint and project schedule, may increase the capacity of the basin by 200,000 gallons by relocating the southern bank 40 feet to the south, as indicated on Sheet C020. Reconstructed bank will maintain a 3 horizontal to 1 vertical slope with a 10 foot wide access road at the top similar to existing condition. Material removed from the bank would be placed and compacted in lifts along the bank's southern
- Deployment and seaming of the HDPE geomembrane replacement liner. The permeability² of geomembrane is typically between 2×10^{-13} and 4×10^{-13} centimeters per second; and
- Placement of cushion and warning layers over the replacement liner.

The warning layer will consist of dense-graded aggregate, grade no. CA6 conforming to Section 1004.01, Coarse Aggregate of State of Illinois, Department of Transportation (IDOT), Standard Specifications for Road and Bridge Construction, or other easily-identifiable material.

The cushion layer will consist of sand, or limestone screenings grade no. FA 1, FA 2, FA3 or FA5 conforming to Section 1003.01 Fine Aggregate of IDOT Standard Specifications for Road and Bridge Construction.

The proposed HDPE geomembrane replacement liner, associated anchor trenches, and cushion and warning layers are shown on Sheet C030. Cross sections and details associated with the liner and cushion/warning layers are shown on Sheets C031 and C032.

² Koerner, Robert M., and David E. Daniel, Final Covers for Solid Waste Landfills and Abandoned Dumps, ASCE Press, 1997

Mr. Jaime Rabins, Div. of Water Pollution Control, IEPA June 30, 2010 Page 3

If you have any questions or require additional information as you review this application, please call me at 630 771 7862.

Sincerely,

Maria Race

Environmental Program Director

Attachments: Figure 1 – Site Location Map

Appendix A - WPC-PS-1 and Schedules G, J and N

Appendix B - Site Photographs

Appendix C - Specification Section 02600, HDPE Geomembrane

Sheet C010 – Existing Conditions Sheet C020 - Liner Subgrade Preparation Sheet C030 - Warning Layer Plan Sheet C031 - Details and Sections

Sheet C032 - Details and Sections

Mr. Mark Kelly, MWG-Powerton cc:

Ms. Heather Simon, Natural Resource Technology, Inc.

1


300

37

Gr.

FIGURES

FIGURE



APPENDIX A

APPENDIX A WPC-PS-1 AND SCHEDULES G, J AND N



Illinois Environmental Protection Agency Permit Section, Division of Water Pollution Control P.O. Box 19276 Springfield, Illinois 62794-9276

For IEPA Use:	

Application for Permit or Construction Approval WPC-PS-1

1.	Owner Name: Midwest Generation EME, LLC							
	Name of Project: Powerton Bypass Basin Liner I	Replacem	ent	1				
	Township: T24N		County: Tazewell	11 11 3 297				
2.	Brief Description of Project:		Ti Zi ritelini	tile 2				
	Maintenance on Bypass Basin Includes replacer be no significant changes to current operation of 200,000 gallons by relocating the southern bank	f the pond	. MWG may increase the capacity of the ba					
3.	Documents Being Submitted: If the Project involute and check the appropriate boxes.	ves any o	f the items listed below, submit the correspondent	onding schedule				
	Private Sewer Connection/Extension Sewer Extension Construct Only Sewage Treatment Works Excess Flow Treatment Lift Station/Force Main	ichedule A/B	Spray Irrigation Septic Tanks Industrial Treatment/Pretreatment Waste Characteristics Erosion Control Trust Disclosure	Schedule H				
	Pekin, IL	25	No. of Page	es: <u>5</u>				
	Specifications: Title Section 02600, High Densi	ty Polyeth	ylene (HDPE) Geomembrane					
			No. of Books/Pages	: 21				
	Other Documents: Facility photos (see attached (Please Specify))						
3.1	Illinois Historic Preservation Agency approval lett	er: Yes []No ☑					
1.	Land Trust: Is the project identified in item numb land which is the subject of a trust? Yes No	er 1 herei 7	n, for which a permit is requested, to be cor	nstructed on				
	If yes, Schedule T (Trust Disclosure) must be contrustee or trust officer.	mpleted a	nd item number 7.1.1 must be signed by a t	peneficiary,				
5.	This is an Application for (Check Appropriate Line	e):						
	 A. Joint Construction and Operating Permit ☑ B. Authorization to Construct (See Instruction ☑ C. Construct Only Permit (Does Not Include) ☑ D. Operate Only Permit (Does Not Include) 	ons) NPDE Operation	ns)					
			•					



6. Certifications and Approval:

6.1

I hereby certify that I am familiar with the information indicated above, and that to the best of my knowledge. The plans and specifications (specifications other the Agency) as described above were prepared by me of	ge and belief such info an Standard Specifica	ormation is true, complete and accurate. ations or local specifications on file with this
Engineer Name: Heather M. Simon		MILLINO COMP
Registration Number: 082 - 060491 (6 digits)		HEATHER M. TO SIMON GOZ.OGC4S1 WATERTOWN WI
Firm: Natural Resource Technology, Inc.		G02.060491 WATERTOWN
Address: 23713 W. Paul Rd, Suite D		WI WILLIAM WIL
		MINIS ONAL EN MILITA
City: Pewaukee	ate: WI Zip: 5307	2 Phone No:
Signature X Worther Smen	/	Date: 7/1/10
Certifications and Approvals for Permits:		
7.1 Certificate by Applicant(s) I/We hereby certify that I/we have read and thorough and am/are authorized to sign this application in acc Control Board. !/We hereby agree to conform with the made part of this Permit.	ordance with the Rule	s and Regulations of the Illinois Pollution
7.1.1 Name of Applicant for Permit to Construct: Mi Address: 13082 E Manito Road	OWES GENERALDIT EV	IE. LLO
City: Pekin	State: IL	Zip Code: 61554
Signature X Maraha		Date: 0.7-6-10
Printed Name: Mike Hanrahan		Phone No:
Title:	No.	COOL OHIEA CONTRACTOR TO SAVESTIVE
Organization:	100.00	
7.1.2 Name of Applicant for Permit to Own and Ope	rate: Same as above	
Address:	(M) (E)	DC 46/4 Carta / Service IIII III A 4.0 g/GC
City:	State:	Zip Code:
Signature X		Date:
Printed Name:		Phone No:
Title:		

Certificate by Design Engineer (When required: refer to instructions)

7.2	2 Attested (Required When Applicant is a Unit of Government) N/A	
Sign	gnature X	Date:	
Title:	de:		
	(Ci	y Clerk, Village Clerk, Sanitary	District Clerk, Etc
7.3	Applications from non-governmental applicants which are no principal executive officer of at least the level of vice preside	ot signed by the owner, must be ont, or a duly authorized represe	e signed by a entative.
7.4	Certificate By Intermediate Sewer Owner N/A		
	I hereby certify that (Please check one):		
	1. The sewers to which this project will be tributary have at wastewater that will be added by this project without cau. Act or Subtitle C. Chapter I, or	dequate reserve capacity to training a violation of the environm	nsport the nental Protection
	2. The Illinois Pollution Control Board, in PCB variance from Subtitle C, Chapter I to allow construction	dated	granted a
}	Name and location of sewer system to which this project will be	tributary:	
- -	Sewer System Owner:	1.5	194
	Address:		16
	City:Sta		E Stalle
	Signature X		
	Printed Name:		
7	Title:		
7	7.4.1 Additional Certificate By Intermediate Sewer Owner N/		
ı	I hereby certify that (Please check one):		
١	The sewers to which this project will be tributary have accurate wastewater that will be added by this project without cau. Act or Subtitle C. Chapter I, or	using a violation of the environn	nental Protection
	2. The Illinois Pollution Control Board, in PCB variance from Subtitle C, Chapter I to allow construction	dateddated	granted a
	3. Not applicable	Tachines that are are socject of	ина арриосион.
١	Name and location of sewer system to which this project will be	tributary:	
5	Sewer System Owner:		
	Address:		
	City: St		
_		Dake	

Title: Certificate By Waste Treatment Works Owner N/A I hereby certify that (Please check one): 1. The waste treatment plant to which this project will be tributary has adequate reserve capacity wastewater that will be added by this project without causing a violation of the Environmental Act or Subtitle C, Chapter I, or 2. The Illinois Pollution Control Board, in PCB	
I hereby certify that (Please check one): 1. The waste treatment plant to which this project will be tributary has adequate reserve capacity wastewater that will be added by this project without causing a violation of the Environmental Act or Subtitle C, Chapter I, or 2. The Illinois Pollution Control Board, in PCB	
□ 1. The waste treatment plant to which this project will be tributary has adequate reserve capacity wastewater that will be added by this project without causing a violation of the Environmental Act or Subtitle C, Chapter I, or □ 2. The Illinois Pollution Control Board, in PCB	
wastewater that will be added by this project without causing a violation of the Environmental Act or Subtitle C, Chapter I, or The Illinois Pollution Control Board, in PCB	
	ty to treat the
I also certify that, if applicable, the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities that the industrial waste discharges described in the application are capabilities and industrial waste discharges described in the application are capabilities and industrial waste discharges described in the application are capabilities and industrial waste discharges described in the application are capabilities. Address:	iance from of this
I also certify that, if applicable, the industrial waste discharges described in the application are capable treated by the treatment works. Name of Waste Treatment Works: Waste Treatment Works Owner: Address: City: State: Date:	
Address:	
Address:	
Signature X Date:	1
Printed Name: Phone No:	
Title:	- E

Please return completed form to the following address:

Illinois Environmental Protection Agency Permit Section, Division of Water Pollution Control P.O. Box 19276 Springfield, Illinois 62794–9276

This Agency is authorized to require this information under litinois Revised Statues, 1979, Chapter 111 1/2, Section 1039. Disclosure of this information is required under that Section. Failure to do so may prevent this form from being processed and could result in your application being denied. This form has been approved by the Forms Management Center.

IL 532-0010 WPC 150 This Agency is authorized to require this information under tilinois Revised Statutes, 1979, Chapter 111 1/2, Section 1039. Disclosure of this information is required under that section. Failure to do so may prevent this form from being processed and could result in your application being denied.

For IEPA Use:	
LOG#	
DATE RECEIVED:	

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL PERMIT SECTION Springfield, Illinois 62794-9276

SCHEDULE G SLUDGE DISPOSAL & UTILIZATION

Ge	neral Ir	nformation		
2.1	Sour	ce(s) Coal Ash from power generation statio	n A	office floor in the
2.2	Prod	uction Volume per 6 yea <u>rs 1000 tons</u>	Dry Tons per year	NA
2.3	Slud	ge to be disposed of is: Liquid NA	Dry Tons NA	The half
2.4	Sludg	ge is: Aerobically digested 🔲 , Anaerobically di	gested 🔲 , Heat Anaerobically	digested . Raw ., Cher
	Stabi	lized 🔲 , Composted 🔲 , Wastewater Lagoon	, WTP Lime , WTP Alun	n 🔲 , WTP fron 🔲 , Other 🛭
	If oth	er, describe Coal Ash	Abture 🔲 , If mixture, describe	
2.5	Is the	sludge defined as hazardous by State or Federa	I Law? YES NO 🗵 . If	yes, basis.
2.6		edge to be stored on the STP site? YES NO		
2.7	Slud	ge Hauling		
	271	Name(s), address(es) and Illinois Transporters	LD Numbers	
		Dave Clinard Trucking - DOT# 280869 Route 24 West; Mt. Sterling, IL 62353		O O CONCERNIT
	2.7.2	For industrial generators, has Illinois Generator If no, contact the Division of Land Pollution Cont		Number been issued? YES
		Illinois Generator ID Number ILD000665471		11 1:6=0 ==
		Authorization Number 9290-99	THE THING WALL	IS SER
Ме	thods o	of Studge Disposal and/or Utilization		
3.1	Land	Application	10,000	
	311	Indicate the number of dry tons of sludge per ye	ar to be disposed by each of the	e following methods:
	•	Agricultural land . Commercial Fertilizer Pro		
		Reclamation ☒ , Silviculture ☐ , Horticultural		
		If other, specify		
	3.12	Studge Disposal Site Location. Provide a map (map) showing location.
	5.1.2			
		Name of USGS Quadrangle Map (7.5 or 15 min	ute) or plat map	
	3.1.3	Provide soil survey map and soil description for	disposal site. Identify name of	soil survey and map sheet nu

3.1.4	Is sludge to be stored at disposal cubic feet.	Isite? YES NO . If yes	s, describe and state the storage volume NA	
3.1.5	Provide a copy of sludge user info	ormation sheet and completed,	signed copies for any known users.	
	Charles Avenue			
3.1.6	In a narrative description provide pollution, potable water supply we total acres available, soil characte	llhead protection and other buffe	on features to prevent ground and/or surface was rdistances, calculations supporting storage capses, etc.	vate acity
	Disposed at Coal Mine once e Buckheart Mine 22116 E County 6 Hwy Canton, IL 61520	very 6 years at:		
3.1.7	23/264	TELVISE TO THE	, organic loading and metal loading rate.	
3.2 Land	filling on-site off-	site	The last section of the last section is a section of the last sect	
3.2,1	Sanitary Landfill Special Walf other, specify	iste Landfill	aste Landfili Other	
3.2.2	Name and Location of Landfill(s)	= w/	Mayor to all graphics	
		E - 77 9 8	A Property of the Control of the Con	
3.2.3	IEPA Permit Number(s)			
0.0 1!				
3,3 Incine				
3.3.1	Name and Location NA			
3.3.2	IEPA Permit Number(s)			
3.3.3	Ultimate Disposal of Incinerator r	esidue		
		Total State of Mississippi		
	<i>3</i> 2	2000		
4. Sludge Cl	haracteristics			
performe	omplete analyses of sludge charact d unless the sludge is disposed of parameters below:	teristics in mg/kg dry wt. basis by Incineration or at an off-site	unless otherwise indicated. The analyses sha andfill. Analyses performed shall include but re	ıll b ot b
Parameti	•	Parameter		
% TS		Sulfur		
% VS		Aluminum (total)		
COD mg/l pH		Arsenic (total) Barium (total)	(cd) (c) (c) (c) (c) (c) (c) (c) (c) (c) (c	
BOD _s mg/	-elimui _ii sivi ii iissa	Cadmium (total)		
	eq of CaCO3 at pH	Cobalt (total)		
•	meq of CaCO3 at pH	Chromium, hex (total)		
	rease mg/l	Chromium (total)		
Phenois r	ng/i	Copper (total)	PASH - N. P. 11	
Cyanide Sulfate (to	otal) ma/l	iron (total) Mercury (total)		
Sulfide (to	- · -	Manganese (total)		
Sodium		Molybdenum (total)		
EC mmho	os/cm	Nickel (total)		
TOC		Lead (total)		

40

ě.

R

10

25

Ammonia mg/l
Total Kjeldahl Nitrogen mg/l
Phosphorus
Potassium
% Volatile Acids, if anaerobically digested

Selenium (total) Vanadium (total) Zinc (total) Radium 226 pCi/g Radium 228 pCi/g Other*

*Include results of any hazardous waste characteristics tests performed for: 1) EP Toxicity, 2) Corrosivity, 3) Ignitability, and 4) Reactivity.

IL 532-0016



ANALYTICAL REPORT

Job Number: 500-22894-1

Job Description: Powerton Basin Sampling

For:

Midwest Generation EME LLC 13082 E Manito Road Pekin, IL 61554

Attention: Mr. Joe Heredia

Cindy Pritchard

Approved for release Cirdy R Pritchard Project Mgmt. Assistan 12/14/2009 12:35 PM

Designee for
Bonnie M Stadelmann
Project Manager II
bonnie.stadelmann@testamericainc.com
12/14/2009

cc: Mark Kelly Ms. Maria Race

These test results meet all the requirements of NELAC for accredited parameters.

The Lab Certification ID# is 100201. TestAmerica Portland OR00040

All questions regarding this test report should be directed to the TestAmerica Project Manager whose signature appears on this report. All pages of this report are integral parts of the analytical data. Therefore, this report should be reproduced only in its entirety.

TestAmerica Laboratories, Inc.
TestAmerica Chicago 2417 Bond Street, University Park, IL 60484
Tel (708) 534-5200 Fax (708) 534-5211 www.testamericaioc.com



SAMPLE RESULTS

TestAmerica Chicago

12/14/2009

Mr. Joe Heredia Midwest Generation EME LLC 13082 E Manito Road Pekin, IL 61554

Client Sample ID: BY-PASS BASIN Lab Sample ID: 500-22894-3

Job Number: 500-22894-1

旗

*

Date Sampled: 12/02/2009 1330 Date Received: 12/04/2009 1030

Client Matrix: Solid

Prep Method: 3010A	Analyte	Result/Qualifier	Unit	RL	Dilution
Prep Nethod: 3010A	Method: TCLP-6010B		Date Analyzed:	12/08/2009 1708	
Barium	Prep Method: 3010A				
Cadmium	Arsenic	<0.050	mg/L	0.050	1.0
Chromium	Barium	0.85	mg/L	0.50	1.0
Case	Cadmium	<0.0050	rng/L	0.0050	1.0
Selenium	Chromium	<0.025	mg/L	0.025	1.0
Date Analyzed: 12/07/2009 2340 Date Prepared: 12/07/2009 0758 Date Prepared: 12/07/2009 0758 Date Prepared: 12/08/2009 1005 Date Prepared: 12/08/2009 1005 Date Prepared: 12/07/2009 0758 Date Prepared: 12/07/2009 0758 Date Prepared: 12/07/2009 0758 Date Prepared: 12/09/2009 1007 Date Prepared: 12/09/2009 1107 Date Prepared: 12/09/2009 0710 Date Prepared: 12/09/2009 0710 Date Prepared: 12/09/2009 0710 Date Prepared: 12/09/2009 0710 Date Prepared: 12/09/2009 0749 Date Prepared: 12/09/2009 0749 Date Prepared: 12/09/2009 1008 Date Prep	Lead	<0.050	mg/L	0.050	1.0
Date Analyzed: 12/07/2009 2340	Selenium	<0.050	mg/L	0.050	1.0
Date Prepared: 12/07/2009 0758 Prepared: 12/07/2009 0759 Prepared: 12/07/2009 0755 Prepared: 12/07/2009 0022 Prepared: 12/07/2009 00	Silver	<0.025	mg/L	0.025	1.0
Potassium 3200 mg/Kg 49 1.0	Method: 6010B		Date Analyzed:	12/07/2009 2340	
Method: \$010B	Prep Method: 3050B		Date Prepared:	12/07/2009 0758	
Date Prepared: 12/07/2009 0758 Sodium 7900 mg/Kg 99 1.0	Potassium	3200	mg/Kg	49	1.0
Date Analyzed: 12/09/2009 1107 Date Analyzed: 12/09/2009 1107 Date Prepared: 12/09/2009 0710 Date Analyzed: 12/09/2009 0710 Date Prepared: 12/09/2009 0710 Date Prepared: 12/09/2009 0710 Date Analyzed: 12/09/2009 0749 Date Analyzed: 12/09/2009 0749 Date Analyzed: 12/09/2009 0749 Date Analyzed: 12/09/2009 1448 Date Prepared: 12/09/2009 1448 Date Prepared: 12/09/2009 1100 Date Analyzed: 12/09/2009 1100 Date Analyzed: 12/09/2009 1100 Date Analyzed: 12/11/2009 0925 Date Prepared: 12/11/2009 0925 Date Prepared: 12/11/2009 0925 Date Analyzed: 12/09/2009 2231 Date Analyzed: 12/09/2009 2231 Date Analyzed: 12/09/2009 2231 Date Analyzed: 12/09/2009 1437 Date Analyzed: 12/09/2009 1430 Date Prepared: 12/10/2009 0755 Date Prepared: 12/09/2009 1430 Date Prepared: 12/09/2009 1430	Method: 6010B		Date Analyzed:	12/08/2009 1005	
Method: TCLP-7470A	Prep Method: 3050B		Date Prepared:	12/07/2009 0758	
Prep Method: 7470A Date Prepared: 12/09/2009 0710 mg/L	Sodium	7900	mg/Kg	99	1.0
Mercury <0.0020 mg/L 0.0020 1.0 Method: Soluble-305.1 Date Analyzed: 12/09/2009 0749 Acidity 200 1.0 Method: 9014 Date Analyzed: 12/09/2009 1448 200 1.0 Method: 9018 Date Prepared: 12/09/2009 1100 1.0 Cyanide, Total <0.43 mg/Kg 0.43 1.0 Method: 9034 Date Analyzed: 12/11/2009 1403 1.0 Prep Method: 9030B Date Prepared: 12/11/2009 0925 1.0 Method: 9038 Date Prepared: 12/08/2009 0002 1.0 Prep Method: 300_Prep Date Prepared: 12/08/2009 0002 1.0 Method: 9045C Date Analyzed: 12/08/2009 1437 1.0 Method: 9046 SU 0.200 1.0 Method: 9046 Date Analyzed: 12/10/2009 0755 1.0 Method: 9046 Date Prepared: 12/10/2009 0755 1.0 Metho	Method: TCLP-7470A		Date Analyzed:	12/09/2009 1107	
Date Analyzed: 12/09/2009 0749 No.	Prep Method: 7470A		Date Prepared:	12/09/2009 0710	
Acidity <200 mg/Kg 200 1.0 Method: 9014 Prep Method: 9010B Cyanide, Total <0.43 mg/Kg 12/09/2009 1448 Prep Method: 9034 Prep Method: 9034 Prep Method: 9030B Sulfide <25 mg/Kg 12/11/2009 0925 Sulfide <25 mg/Kg 25 1.0 Method: 9038 Prep Method: 300_Prep Date Prepared: 12/08/2009 2231 Sulfate 62 mg/Kg 51 1.0 Method: 9046C pH 6.86 SU 0.200 1.0 Method: 9066 Prep Method: Date Analyzed: 12/10/2009 0755 Prep Method: Date Prepared: 12/10/2009 1430 Prep Method: Total Recoverable 7.8 mg/Kg 0.49 1.0	Mercury	<0.0020	mg/L	0.0020	1.0
Method: 9014 Date Analyzed: 12/09/2009 1448 Prep Method: 9010B Date Prepared: 12/09/2009 1100 Cyanide, Total <0.43 mg/Kg 0.43 1.0 Method: 9034 Date Analyzed: 12/11/2009 1403 Prep Method: 9030B Date Prepared: 12/11/2009 0925 Sulfide <25 mg/Kg 25 1.0 Method: 9038 Date Analyzed: 12/08/2009 0002 Prep Method: 300_Prep Date Prepared: 12/06/2009 2231 Sulfate 62 mg/Kg 51 1.0 Method: 9046C Date Analyzed: 12/08/2009 1437 Prep Method: 9046 Date Analyzed: 12/10/2009 0755 Prep Method: Date Prepared: 12/09/2009 1430 Prep Method: Date Prepared: 12/09/2009 140 Prep Method: Date Prepared: 12/10/2009 0755 Prep Method:	Method: Soluble-305.1		Date Analyzed:	12/09/2009 0749	
Date Prepared: 12/09/2009 1100	Acidity	<200	mg/Kg	200	1.0
Cyanide, Total <0.43 mg/Kg 0.43 1.0 Method: 9034 Date Analyzed: 12/11/2009 1403 Date Prepared: 12/11/2009 0925 Date Prepared: 12/11/2009 0925 1.0 Method: 9038 Date Analyzed: 12/08/2009 0002 Date Prepared: 12/06/2009 2231 Date Prepared: 12/06/2009 2231 1.0 Method: 9046C Date Analyzed: 12/08/2009 1437 51 1.0 Method: 9046 Date Analyzed: 12/10/2009 0755 1.0 Prep Method: Distiil/Phenol Date Prepared: 12/10/2009 1430 1.0 Phenolics, Total Recoverable 7.8 mg/Kg 0.49 1.0	Method: 9014			12/09/2009 1448	
Method: 9034 Date Analyzed: 12/11/2009 1403 Prep Method: 9030B 25 1.0 Method: 9038 Date Analyzed: 12/08/2009 0002 Prep Method: 300_Prep Date Prepared: 12/06/2009 2231 Sulfate 62 mg/Kg 51 1.0 Method: 9046C Date Analyzed: 12/08/2009 1437 pH 6.86 SU 0.200 1.0 Method: 9066 Date Analyzed: 12/10/2009 0755 Prep Method: Distil/Phenol Date Prepared: 12/09/2009 1430 Phenolics, Total Recoverable 7.8 mg/Kg 0.49 1.0	Prep Method: 9010B		Date Prepared:	12/09/2009 1100	
Prep Method: 9030B Date Prepared: 12/11/2009 0925 Sulfide <25 mg/Kg 25 1.0	Cyanide, Total	<0.43	mg/Kg	0,43	1.0
Sulfide <25 mg/Kg 25 1,0 Method: 9038 Date Analyzed: 12/08/2009 0002 2231 Prep Method: 300_Prep Date Prepared: 12/06/2009 2231 1,0 Sulfate 62 mg/Kg 51 1,0 Method: 9045C Date Analyzed: 12/08/2009 1437 200 1,0 Method: 9045 Date Analyzed: 12/10/2009 0755 1,0 Prep Method: Distiil/Phenol Date Prepared: 12/09/2009 1430 1,0 Phenolics, Total Recoverable 7.8 mg/Kg 0.49 1,0			Date Analyzed:	12/11/2009 1403	
Method: 9038 Prep Method: 300_Prep Date Prepared: 12/08/2009 0002 Date Prepared: 12/06/2009 2231 Sulfate 62 Method: 9045C Date Analyzed: 12/08/2009 1437 DATE Analyzed: 12/08/2009 1437 DATE Analyzed: 12/08/2009 1437 DATE Analyzed: 12/10/2009 0755 Prep Method: Date Prepared: 12/10/2009 1430 Phenolics, Total Recoverable 7.8 Method: 9066 Date Analyzed: 12/10/2009 0755 Date Prepared: 12/09/2009 1430 Method: Olstifi/Phenol			Date Prepared:	12/11/2009 0925	
Date Prepared: 12/06/2009 2231 Sulfate 62 mg/Kg 51 1.0	Sulfide	<25	mg/Kg	25	1.0
Sulfate 62 mg/Kg 51 1.0 Method: 9045C Date Analyzed: 12/08/2009 1437 pH 6.86 SU 0.200 1.0 Method: 9066 Date Analyzed: 12/10/2009 0755 Prep Method: Distiil/Phenol Date Prepared: 12/09/2009 1430 Phenolics, Total Recoverable 7.8 mg/Kg 0.49 1.0	Method: 9038		Date Analyzed:	12/08/2009 0002	
Method: 9045C Date Analyzed: 12/08/2009 1437 pH 6.86 SU 0.200 1.0 Method: 9066 Date Analyzed: 12/10/2009 0755 Prep Method: Distil/Phenol Date Prepared: 12/09/2009 1430 Phenolics, Total Recoverable 7.8 mg/Kg 0.49 1.0	Prep Method: 300_Prep		Date Prepared:	12/06/2009 2231	
pH 6.86 SU 0.200 1.0 Method: 9066 Date Analyzed: 12/10/2009 0755 Prep Method: Distifl/Phenol Date Prepared: 12/09/2009 1430 Phenolics, Total Recoverable 7.8 mg/Kg 0.49 1.0	Sulfate	62	mg/Kg	51	1.0
Method: 9096 Date Analyzed: 12/10/2009 0755 Prep Method: Date Prepared: 12/09/2009 1430 Phenolics, Total Recoverable 7.8 mg/Kg 0.49 1.0	Method: 9045C		Date Analyzed:	12/08/2009 1437	
Prep Method: Distrit/Phenol Date Prepared: 12/09/2009 1430 Phenolics, Total Recoverable 7.8 mg/Kg 0.49 1.0	pH	6.86	SU	0.200	1.0
Phenolics, Total Recoverable 7.8 mg/Kg 0.49 1.0	Method: 9066		Date Analyzed:	12/10/2009 0755	
	Prep Method: Distil/Phenol		Date Prepared:	12/09/2009 1430	
Method: 9071B Date Analyzed: 12/09/2009 1428	Phenolics, Total Recoverable	7.8	mg/Kg	0.49	1.0
	Method: 9071B		Date Analyzed:	12/09/2009 1426	

Page 15 of 66

12/14/2009

Mr. Joe Heredia Midwest Generation EME LLC 13082 E Manito Road Pekin, IL 61554 Job Number: 500-22894-1

Client Sample ID: BY-PASS BASIN Lab Sample ID: 500-22894-3

Date Sampled: 12/02/2009 1330 Date Received: 12/04/2009 1030

Client Matrix: Solid Percent Solids: 97

Analyte	Result/Qualifier	Unit	RL	Dilution
Prep Method: 9071B HEM (Oil & Grease)	<510	Date Prepared: mg/Kg	12/09/2009 0825 510	1.0
Method: Lloyd Kahn TOC Dup	2300	Date Analyzed: mg/Kg	12/11/2009 1021 120	1.0
Method: Moisture Percent Moisture	3.1	Date Analyzed: %	12/06/2009 2340 0.10	1.0
Method: Soluble-SM 2320B Alkalinity	<430	Date Analyzed: mg/Kg	12/08/2009 1009 430	1.0
Method: SM 4500 NH3 C Prep Method: SM 4500 NH3 B Ammonia	<20	Date Analyzed: Date Prepared: mg/Kg	12/10/2009 1150 12/09/2009 1120 20	1.0
Method: SM 4500 Norg C Prep Method: 351.3_Prep Nitrogen, Kjeldah!	42	Date Analyzed: Date Prepared: mg/Kg	12/07/2009 1637 12/07/2009 1405 40	1.0
Method: SM 4500 P E Prep Method: SM 4500 P B Phosphorus as P	1200	Date Analyzed: Date Prepared: mg/Kg	12/10/2009 1404 12/08/2009 1100 230	25
Method: 8M 5210B Biochemical Oxygen Demand	<21	Date Analyzed: mg/Kg	12/04/2009 1610 21	10
Method: SM 5220C Prep Method: SM 5220 Chemical Oxygen Demand	27000	Date Analyzed: Date Prepared: mg/Kg	12/08/2009 1107 12/07/2009 1520 1700	10

FOR IEPA USE: LOG # DATE RECEIVED:

5

St.

98

3

*

超

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL PERMIT SECTION

Springfield, Illinois 62706


SCHEDULE J INDUSTRIAL TREATMENT WORKS CONSTRUCTION OR PRETREATMENT WORKS


1.2	Plant	Location	Contract			_	-77	V	11
	1.2.1	SV	<u> </u>	9		T24N	R5W_		
		Quarter S	ection	Section	To	wnship	Range		P.M.
		Latitude	_	deg	32	min	80	_ sec.	"NORTH
		Longitude		deg.	40	min	90	sec.	"WEST
				Map (7.5 or 15					per l'or
NAF	RATIVE	DESCRIPTION	N AND SCHE	MATIC WASTE	FLOW DIAG	RAM: (see inst	ructions)		THE RESERVE
				ery 6 years or s ched waste flo		weeks during	maintenance/o	ff-line of	the Primary
2.1	PRIN	CIPAL PRODU	CTS:						
	elect	rical power	- 7.0	M					100
		mi see							All See Inc.
2.2	DRIM	CIPAL RAW M	ATERIAL C.	Care III				541.00	Type The 1977
4.2		OIFAL RAYY MV	HIERIALS.	- IVIII-					
	coal	1078 F F							referred the
									The street of the
<u>DES</u> 3.1	Subm		n through all t	reatment units sh					surface settling rate
	Subm weir o Waste Subm	nit a flow diagran overflow rate, and o Treatment Wo nit plans and sp	n through all t nd other perti orks is: Batcl ecifications fo	reatment units shoent design data Conting r proposed cons	. Include hyd wous 図 truction.	Iraulic profiles a , No. of Batche	on times, organic le nd description of es/day,	monitorir	ng systems.
3.1 3.2 3.3 3.4 DIR If re	Subm weir of Waste Subm Disch ECT DIS ceiving si	nit a flow diagram overflow rate, and or Treatment Wo nit plans and sp arge is: Existin CHARGE IS To tream or storm	n through all to nd other perti- orks is: Batch ecifications for ng \(\subseteq \) ; \(\subseteq \) Receiving sewer are inc	reatment units shoent design data Conting reproposed cons Will begin on _ Stream Muticated complete	. Include hydrous truction. Inicipal Sanitz the following	Iraulic profiles a , No. of Batche ary Sewer D	nd description of es/day, Municipal storm o	monitorir No. of St	ng systems.
3.1 3.2 3.3 3.4 DIR If re	Subm weir of Waste Subm Disch ECT DIS ceiving st	ait a flow diagrar everflow rate, and Treatment Wo hit plans and sp arge is: Existin CHARGE IS To tream or storm eiving stream	n through all to not other pertions is: Batchecifications for a constant of the constant of th	reatment units sheet design data Continue Construction proposed cons Will begin on Stream Mudicated complete hannel	Include hydenuous truction. Inicipal Sanitz the following	Iraulic profiles a , No. of Batche ary Sewer itributary to Illi	nd description of es/day, Municipal storm o inois River	monitorir No. of St r municip	ng systems. nifts/day
3.1 3.2 3.3 3.4 DIR If re Nam tribu	Subm weir of Waste Subm Disch ECT DIS ceiving sine of rece stary to	ait a flow diagram everflow rate, an e Treatment Wo iit plans and sp earge is: Existin CHARGE IS To tream or storm eiving stream	n through all to nd other perti- orks is: Batcl ecifications for ng ⊠ : 2: Receiving sewer are inc Old Intake C	reatment units shent design data Continer proposed cons Will begin on Stream Mu dicated complete hannel	. Include hydrous 🖾 struction.	Iraulic profiles a , No. of Batche ary Sewer tributary to Illi	nd description of es/day, Municipal storm of inois River	monitorir No. of St or municip	ng systems. ilfts/day hal combined sawe
3.1 3.2 3.3 3.4 DIR If re Nantribu	Subm welr of Waste Subm Disch ECT DIS ceiving so the of receivitary to	ait a flow diagram overflow rate, as the Treatment Would plans and spirarge is: Existin CHARGE IS To tream or storm eiving stream ent works subject	n through all to not other pertitions is: Batclecifications for a sewer are incoded intake C	reatment units shoent design data Continor proposed cons Will begin on Stream Mu dicated complete hannel Yes No	. Include hydrous itruction. Inicipal Sanitz the following ; tributary	raulic profiles a , No. of Batche ary Sewer tributary to Illi	nd description of es/day, Municipal storm of inois River,	monitorir No. of St or municip	ng systems. nifts/day
3.1 3.2 3.3 3.4 DIR If re Nantribu	Subm welr of Waste Subm Disch ECT DIS ceiving so the of receivitary to	ait a flow diagram overflow rate, as the Treatment Would plans and spirarge is: Existin CHARGE IS To tream or storm eiving stream ent works subject	n through all to not other pertitions is: Batclecifications for a sewer are incoded intake C	reatment units shent design data Continer proposed cons Will begin on Stream Mu dicated complete hannel	. Include hydrous itruction. Inicipal Sanitz the following ; tributary	raulic profiles a , No. of Batche ary Sewer tributary to Illi	nd description of es/day, Municipal storm of inois River,	monitorir No. of St or municip	ng systems. ilfts/day hal combined sawe
3.1 3.2 3.3 3.4 DIR If re Nan tribu	Subm welr of Waste Subm Disch ECT DIS ceiving so the of receivitary to	ait a flow diagram overflow rate, as the Treatment Would plans and spirarge is: Existin CHARGE IS To tream or storm eiving stream ent works subject	n through all to not other pertitions is: Batclecifications for a sewer are incoded intake C	reatment units shoent design data Continor proposed cons Will begin on Stream Mu dicated complete hannel Yes No	. Include hydrous itruction. Inicipal Sanitz the following ; tributary	raulic profiles a , No. of Batche ary Sewer tributary to Illi	nd description of es/day, Municipal storm of inois River,	monitorir No. of St or municip	ng systems. ilfts/day pal combined sawe
3.1 3.2 3.3 3.4 DIR If re Nan tribu is th	Subminiment well control waste Subminiment would be subminiment.	ait a flow diagram everflow rate, an e Treatment Wo iit plans and sp earge is: Existin CHARGE IS To tream or storm eiving stream ent works subjects datum) and	n through all to ad other pertions is: Batchecifications for the control of the c	reatment units shoent design data Continer proposed cons Will begin on _ Stream	. Include hyduous	raulic profiles a No. of Batche ary Sewer tributary to Illit to at is the maximate the flooding	nd description of es/day, Municipal storm of inois River,	monitorir No. of St or municip	ng systems. ilfts/day pal combined sawe
3.1 3.2 3.3 3.4 DIR If re Nan tribu Is the	Submin well of Waste Submin Disch ECT DIS ceiving some of receiving the control of the control o	ait a flow diagram everflow rate, as a Treatment Wo ait plans and sp arge is: Existin CHARGE IS To tream or storm eiving stream ent works subje orks datum) and	n through all to not other pertitions is: Batcle edifications for the control of	reatment units shoent design data Continuer proposed cons Will begin on Stream Mulicated complete hannel Yes No ions have been mated constructions	Include hydrous struction. Inicipal Sanitz the following: tributary tf so, who add to elimin	raulic profiles a , No. of Batche ary Sewer tributary to Illition to at is the maxim- ate the flooding	nd description of ss/day, Municipal storm of inois River, um flood elevation hazard?	monitorir No. of St or municip	ng systems. ilfts/day pal combined sawe
3.1 3.2 3.3 3.4 DIR If re Nantribu Is th	Subminiment wo	ait a flow diagram everflow rate, as a Treatment Wo ait plans and sp arge is: Existin CHARGE IS To tream or storm eiving stream ent works subje orks datum) and attention 09/01	n through all to and other pertitions is: Batchecifications for a sewer are incoded intake Code intake Code to flooding what provisions is a sewer are incoded intake Code int	reatment units shoent design data Continuer proposed cons Will begin on Stream Mudicated complete hannel Yes No [ons have been mated constructions]	Include hydrous struction. Inicipal Sanitz the following tributary stributary stributary and to eliminate to eliminate of Company stribute of Company stribute of Company stribute of Company stribute s	raulic profiles a , No. of Batche ary Sewer tributary to IIII to IIII at is the maximate the flooding	nd description of es/day, Municipal storm of inois River um flood elevation hazard?	monitorir No. of St or municip	ng systems. ilfts/day pal combined sawe
3.1 3.2 3.3 3.4 DIR If re Nantribu Is the	Subministry to	ait a flow diagram everflow rate, as a Treatment Wo it plans and sp arge is: Existin CHARGE IS To tream or storm eiving stream ent works subje orks datum) and attention 09/01 chedule NA	n through all to and other pertitions is: Batchecifications for a sewer are incoded intake Code intake Code to flooding what provisions is to be a sewer are incoded intake Code intake Co	reatment units shoent design data Continuer proposed cons Will begin on Stream Mudicated complete hannel Yes No [ons have been mated constructions]	Include hydrous struction. Inicipal Sanitz the following: tributary stributary stributary and to eliminate to eliminate of Compate Opera	raulic profiles a , No. of Batche ary Sewer tributary to IIII to IIII at is the maximate the flooding	nd description of es/day, Municipal storm of inois River um flood elevation hazard?	monitorir No. of St or municip	ng systems. ilfts/day pal combined sawe
3.1 3.2 3.3 3.4 DIR If re Nan tribu is th trea APF Star Ope 100	Subm weir c Waste Subm Disch ECT DIS ceiving sine of rece stary to _ te treatment wo PROXIM* t of Constraint So design design	ait a flow diagram overflow rate, as a Treatment Wo it plans and sp arge is: Existin CHARGE IS To tream or storm eiving stream ent works subjectives datum) and attraction 09/01 chedule NA load to be read	n through all to and other pertitions is: Batchecifications for a sewer are incoded intake Code intake Code to flooding what provisions is to be a sewer are incoded intake Code intake Co	reatment units shoent design data Continuer proposed cons Will begin on Stream Mudicated complete hannel Yes No [ons have been mated constructions]	Include hydrous struction. Inicipal Sanitz the following: tributary stributary stributary and to eliminate to eliminate of Compate Opera	raulic profiles a , No. of Batche ary Sewer tributary to IIII to IIII at is the maximate the flooding	nd description of es/day, Municipal storm of inois River um flood elevation hazard?	monitorir No. of St or municip	ng systems. ilfts/day pal combined sawe
3.1 3.2 3.3 3.4 DIR If re Nam tribu is th trea APF Star Ope 100 DES	Subministry to a precious subministry to a p	ait a flow diagram overflow rate, as a Treatment Wo it plans and sp arge is: Existin CHARGE IS To tream or storm eiving stream ent works subjected atum) and attention 09/01 chedule NA load to be reach	n through all to and other pertitions is: Batchecifications for a confection of the	reatment units shoent design data Continuer proposed cons Will begin on _ Stream Muticated complete hannel Yes No ions have been mated constructions	Include hydrous struction. Inicipal Sanitz the following: tributary If so, whade to elimin on schedule: Date of Comp	raulic profiles a , No. of Batche ary Sewer tributary to Illi to lat is the maximulate the flooding	nd description of es/day, Municipal storm of inois River um flood elevation hazard?	monitorir No. of St or municip	ng systems. Inifits/day Pal combined sewe
3.1 3.2 3.3 3.4 DIR If re Nam tributs the Leading Star Ope 100	Subministry to Line treatment wo PROXIMA to Consumation Science Scienc	ait a flow diagram overflow rate, as a Treatment Wo it plans and sp arge is: Existin CHARGE IS To tream or storm eiving stream ent works subje orks datum) and the truction 09/01 chedule NA load to be read ADINGS in population equi	n through all to and other pertitions is: Batchecifications for a construction of the	reatment units shoent design data Conting Conting Front Stream Musticated complete hannel Yes No forms have been mated constructions mated constructions population equiv	Include hydrous struction. Inicipal Sanitz the following: tributary If so, whade to elimin on schedule: Date of Comp	raulic profiles a , No. of Batche ary Sewer tributary to Illi to lat is the maximulate the flooding	nd description of es/day, Municipal storm of inois River um flood elevation hazard?	monitorir No. of St or municip	ng systems. inifis/day pal combined ser
3.1 3.2 3.3 3.4 DIR If re Nan tribu is th trea APE Star Ope 100 DES	Subministry to	ait a flow diagram overflow rate, as a Treatment Wo it plans and sp arge is: Existin CHARGE IS To tream or storm eiving stream eiving stream ent works subjected atum) and attention 09/01 chedule NA load to be read ADINGS in population equal	n through all to and other pertitions is: Batchecifications for a sewer are incoded intake Code to flooding I what provisions is to flooding I what provisions is to flood in the code of	reatment units shoent design data Conting Conting Front Stream Musticated complete hannel Yes No forms have been mated constructions mated constructions population equiv	Include hydrous struction. Inicipal Sanitz the following Tributary If so, whade to elimin In schedule: Date of Comp Date Opera	raulic profiles a , No. of Batche ary Sewer tributary to Illi to lat is the maximulate the flooding	nd description of es/day, Municipal storm of inois River um flood elevation hazard?	monitorir No. of St or municip	ng systems. ilfts/day pal combined sew

	7.3	Design Maximum Flow Rate 32.4 MGD.
	7.4	Design Minimum Flow Rate 10.6 MGD.
	7.5	Minimum 7-day, 10-year low flow NA cfs NA MGD.
		Minimum 7-day, 10-year flow obtained from NA
	7.6	Dilution Ratio_NA :
8.	FLOW	TO TREATMENT WORKS (if existing):
	8.1	Flow every 6 to 7 years
		8.1.1 Average Flow 13.13 MGD
		8.1.2 Maximum Flow 32.4 MGD
	8.2	Equipment used in determining above flows
9.	Has a	preliminary engineering report for this project been submitted to this Agency for Approval?
	Yes [No 🖾 . If so, when was it submitted and approved. Date Submitted
		Certification #
		Dated
10.	List Pe	rmits previously issued for the facility:
	NPDE	S Permit No. IL0002232
	" "	SO CONTROL TO SECONDE
11.	Descri	pe provisions for operation during contingencies such as power failures, flooding, peak loads, equipment failure, maintenance shut
	downs	and other emergencies.
	There	is no equipment in the basin. Influent pumped to basin, so in the event of power failure or equipment
		nction, the flow of influent to the basin stops.
12.	Compl	ete and submit Schedule G if sludge disposal will be required by this facility.
13.	WAST	E CHARACTERISTICS: Schedule N must be submitted.
14.	TREAT	IMENT WORKS OPERATOR CERTIFICATION: List names and certification numbers of certified operators:
	Mark	Kelly (see attached certification)
		, , , , , , , , , , , , , , , , , , ,

IL 532-0018 WPC 158 81

3





MARK S. KELLY

haming fulfilled the requirements therefore, is a Inchificate of

Hardward hairs

COM ED

POWERTON

Mesury this 3rd dupt of suggest A.D. 198

This Agency is authorized to require this information under littnois Revised Statutes, 1979, Chapter 111 1/2, Section 1039. Disclosure of this information is required under that section. Failure to do so may prevent this form from being processed and could result in your application being denied.

1. Name of Project Powerton Bypass Basin Liner Replacement

For IEPA Use:

LOG#

DATE RECEIVED:

ILLINOIS ENVIRONMENTAL PROTECTION AGENCY DIVISION OF WATER POLLUTION CONTROL PERMIT SECTION Springfield, Illinois 62734-6276

SCHEDULE N WASTE CHARACTERISTICS

FLOW DATA	<u>EXISTING</u> <u>PR</u>		OPOSED-DESIGN			
2.1	21.0	300.000	same			
2.2 Maximum Daily Flow (gp	32,400,000		same			
2.3 TEMPERATURE						
- 10	1897					Max. Temp.
Time of	Avg. Intake Temp. F	Avg. Effluent Temp. F	Max. Int		Effluent emp F.	Outside Mixin
SUMMER	NA _	NA	NA	sant N	A	NA
WINTER	NA	NA	NA	N	Α	NA
2.4 Minimum 7-day, 10-year	flow: NA	cfs NA I	MGD.			
2.5 Dilution Ratio: NA	Alt	_				
2.6 Stream flow rate at time	of sampling N	A cfs NA	ММ	GD.		
CONSTITUENT	RAW WASTE (mg/l)	TREATED EFFL Avg. (mg/l) Ma	1.61	UPSTREAM (mg/l)	DOWNS	TREAM SAMPLE (mg/l)
Ammonia Nitrogen (as N)	NA .	NA	됐	NA	NA	S 1 17 52 6
Arsenic (total)	NA	NA	- 1	NA	NA	A97 J. 19
Barium	NA	NA	ЯĪ	NA	NA	
Boron	NA .	NA	2) =	NA	NA	
BOD ₆	NA	NA NA		NA	NA	
Cadmium	NA	NA		NA	NA:	
Carbon Chloroform Extract	NA	NA		NA	NA	
Chloride	NA :	NA		NA	NA	
Chromium (total hexavalent)	NA	NA – ž		NA	NA -	
Chromium (total trivalent)	NA	NA		NA	NA	377

(mg/l)	Avg. (mg/l) Max.	UPSTREAM (mg/l)	DOWNSTREAM SAMPLES (mg/l)
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA SAME AND SAME	NA	NA
NA	NA	NA	NA
NA PART	NA	NA	NA
NA IFATOS	NA	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA THE STATE OF TH
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA -	NA NA	NA
NA	NA	NA	NA
NA	NA sings are	NA	NA
NA	NA	NA	NA MA
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA ESSENTING
NA	NA	NA	NA
NA	NA	NA	NA
NA	NA	NA	NA
		The first	
			District and
	A SE	196	W OF THE RESERVE OF THE
	NA N	NA NA NA NA	NA NA NA

IL 532-0019 WPC 159

tyte Bank grant

-0

APPENDIX B

APPENDIX B SITE PHOTOGRAPHS



Northeast corner of basin looking south along access ramp on October 20, 2009



South end of basin looking north on October 20, 2009



Inlet structure



Looking south at discharge structure on October 20, 2009



Looking southwest at discharge structure on October 20, 2009



Looking northwest at discharge structure on October 20, 2009



Looking west at overflow corrugated metal pipe on October 20, 2009

. 1

意

A.

14

giffyrgan o'i sear y glyc i gelfyd y glychi y glyc y rae ei y y rheffyg.

APPENDIX C

APPENDIX C

SPECIFICATION SECTION 02600, HDPE GEOMEMBRANE

SECTION 02600 HIGH DENSITY POLYETHYLENE (HDPE) GEOMEMBRANE

PART 1 - GENERAL

1.01 WORK INCLUDES

A. Furnish all labor, materials, tools, supervision, transportation, and installation equipment necessary for installation of 60-mil High Density Polyethylene (HDPE) geomembrane, as specified herein, and as shown on Contract Drawings.

1.02 REFERENCE STANDARDS

- A. ASTM D6392 Test Method for Determining the Integrity of Nonreinforced Geomembrane Seams Produced Using Thermo-Fusion Methods.
- B. ASTM D7007 Standard Practice for Locating Leaks in Geomembranes Covered with Water or Earthen Materials.
- GRI Test Method, GM 13 Test Methods, Test Properties and Testing Frequency for High Density Polyethylene (HDPE) Smooth and Textured Geomembranes
- D. GRI Test Method, GM 14 Selecting Variable Intervals for Taking Geomembrane Destructive Seam Samples Using the Method of Attributes.
- E. GRI Test Method, GM 19 Seam Strength and Related Properties of Thermally Bonded Polyolefin Geomembranes.

1.03 DEFINITIONS

- A. Geomembrane Installer: hired by Contractor or Owner responsible for field handling, transporting, storing, deploying, seaming and testing of the geomembrane seams.
- B. Geomembrane Manufacturer: hired by Geomembrane Installer, Contractor, or Owner to provide HDPE geomembrane.
- C. Leak Location Contractor: hired by Contractor or Owner and responsible for locating potential holes in the installed geomembrane using electrical methods.
- D. Geosynthetic Quality Assurance Consultant: Consultant, independent from the Manufacturer, and Installer, responsible for field oversight of geosynthetics installation, and related testing, usually under the direction of the Owner.
- D. Geosynthetic Quality Assurance Laboratory (Testing Laboratory): Laboratory, independent from the Manufacturer and Installer, responsible for conducting laboratory tests on samples of geosynthetics obtained at the site or during manufacturing, usually under the direction of the Owner.

1965 Section 02600 HDPE Geomembrane

NOT FOR CONSTRUCTION

Section 02600-1

- D. Lot: A quantity of resin (usually the capacity of one rail car) used in the manufacture of geomembranes. Finished roll will be identified by a roll number traceable to the resin lot used.
- E. Resin Supplier: selected by Geomembrane Manufacturer to provide resin used in manufacturing geomembrane.
- F. Panel: Unit area of a geomembrane that will be seamed in the field that is larger than 100ft².
- G. Patch: Unit area of a geomembrane that will be seamed in the field that is less than 100ft².
- H. Subgrade Surface: Soil Layer surface which immediately underlies the geosynthetic material(s).

1.04 OUALITY ASSURANCE

A. Qualifications:

- Geomembrane Manufacturer shall have a minimum of 5 years of continuous experience manufacturing HDPE geomembrane totaling 1,000,000 square feet.
- 2. Geomembrane Installer:
 - a. 5 years of continuous experience in installation of HDPE geomembrane.
 - Experience totaling a minimum of 5,000,000 square feet of installed HDPE geomembrane on some combination of at least 10 completed facilities.
 - c. Personnel performing seaming operations qualified by experience or by successfully passing seaming tests. Master seamer shall have experience seaming a minimum of 3,000,000 square feet of geomembrane using same type of seaming apparatus to be used on this project.
- 3. Leak Location Contractor:
 - d. 3 years of continuous experience in performing leak location surveys using electrical methods.
 - e. Experience totaling a minimum of 2,000,000 square feet of geomembrane leak location surveys on some combination of at least 5 completed facilities.
 - f. Personnel performing survey qualified by experience with at least 2 years of geomembrane testing experience using the leak location survey electrical method.
- B. Quality Assurance Program:

1965 Section 02600 HDPE Geomembrane

NOT FOR CONSTRUCTION

- Geomembrane Manufacturer/Installer shall conform with requirements of these Technical Specifications.
- The Owner or Contractor will engage and pay for the services of a Geosynthetic Quality Assurance Consultant and Laboratory to monitor geomembrane installation.

1.05 SUBMITTALS

- A. Prior to project start, submit the following to Geosynthetic Quality Assurance Consultant in accordance with Section 01300, Submittals:
 - 1. Raw Materials:
 - a. Name of Resin Supplier, location of supplier's production plant(s), resin brand name and product number.
 - Source and nature of plasticizers, fillers, carbon black and any other additives along with their percent addition to geomembrane material.
 - Test results documenting conformance with the "index properties" of GRI Test Method, GM 13.
 - 2. Geomembrane Manufacturer's Certification:
 - a. Written certification that Geomembrane Manufacturer's Quality Control Plan was fully implemented during production of geomembrane material supplied for this project. (Submittal shall be made within 5 working days of delivery to site).
 - 3. Geomembrane Installer's Seaming Personnel
 - a. Training completed by personnel.
 - b. Seaming experience for each personnel.
 - 4. Geomembrane Manufacturer Production Information:
 - Corporate background information indicating compliance with qualification requirements.
 - b. Quality control plan for manufacturing.
 - c. Copy of quality control certificates demonstrating compliance with the quality control plan for manufacturing and the test property requirements of GRI Test method, GM 13 (i.e. mill certificates).
 - 5. Geomembrane Installer's Information:

- Corporate background information indicating compliance with qualification requirements.
- List of completed facilities, totaling 5,000,000 square feet minimum for which Geomembrane Installer has completed installation of a HDPE geomembrane. Include name and purpose of facility, location, date of installation, and quantity installed.
- c. Resumes of personnel performing field seaming operation, along with pertinent experience information. Include documentation regarding which seamers are qualified to use thermal fusion welding apparatus.
- d. Installation quality control plan.
- 6. Installation panel layout diagram identifying placement of geomembrane panels, seams, and any variance or additional details which deviate from Contract Drawings or Technical Specifications. Layout shall be drawn to scale and shall be adequate for use as a construction plan. Layout shall include dimensions and pertinent seam and anchorage details.
- 7. Installation Sequence and Schedule shall be included as part of Construction Progress Schedule.
- 8. Description of seaming apparatus to be used.
- With bid, submit the following to Owner and/or Engineer in accordance with Section 01300, Submittals
 - 1. Leak Location Contractor's Work Plan:
 - a. Corporate background information indicating compliance with qualification requirements.
 - b. List of completed facilities, totaling 2,000,000 square feet minimum of geomembrane leak location surveys on some combination of at least 5 completed facilities. Include name and purpose of facility, location, date of survey, survey method, and quantity surveyed.
 - Resumes of personnel performing leak location survey, along with pertinent experience information.
 - Leak Location Contractor quality control plan including description of the proposed survey methods and procedures, and field calibration procedures.
 - Leak Location Contractor's required site preparations to be completed to
 perform the proposed leak location survey, and estimated duration to
 complete the survey.
 - f. An example of a final report (per ASTM D 7007) provided by the Leak Location Contractor following the completion of the survey.

1965 Section 02600 HDPE Geomembrane

- C. During installation, submit the following to the Geosynthetic Quality Assurance Consultant:
 - 1. Daily records/logs prepared by Geomembrane Installer documenting work performed, personnel involved, general working conditions, and any problems encountered or anticipated on project. Submit on a weekly basis.
 - Copy of subgrade acceptance signed by Geomembrane Installer for areas to be covered with geomembrane each day.
- D. Within 10 days of geomembrane installation completion, submit the following to Geosynthetic Quality Assurance Consultant:
 - Geomembrane installation certification that Work was performed under Geomembrane Installer's approved quality control plan and in substantial compliance with Technical Specifications and Contract Drawings.
 - As-built panel diagram identifying placement of geomembrane panels, seams, repairs, and destructive seam sample locations.
 - Copy of warranty for material (including factory seams) and installation covering both for a period of 2 years from the date of substantial completion.
- E. The Geosynthetic Quality Assurance Consultant will review and inspect HDPE geomembrane installation upon completion of all Work specified in this Section. Deficiencies noted shall be corrected at no additional cost to the Owner.
- F. The Geosynthetic Quality Assurance Consultant will provide written final acceptance of the geomembrane installation after completion of material placement above geomembrane. Written conditional geomembrane installation acceptance can be provided to the Contractor prior to completion of material placement above geomembrane when the following conditions are satisfied, if necessary, and requested by the Contractor:
 - The entire geomembrane installation is completed or any pre-determined subsection if the project is phased.
 - 2. All installation quality assurance/control documentation has been completed and submitted to the Geosynthetic Quality Assurance Consultant or Owner.
 - 3. Verification of the adequacy of all field seams, repairs and associated testing is complete.

1.06 DELIVERY, STORAGE, AND HANDLING

- A. Transportation:
 - Geomembrane rolls shall be transported, unloaded and handled at the job site in accordance with manufacturer recommendations. Damaged material may be rejected by the Geosynthetic Quality Assurance Consultant.

1965 Section 02600 HDPE Geomembrane

NOT FOR CONSTRUCTION

B. On-site Storage:

- Geomembrane rolls which have been delivered to job site shall be unloaded and stored in original, unopened packaging in a secure location, determined by Owner and/or Geosynthetic Quality Assurance Consultant.
- 2. Store geomembrane rolls to ensure adequate protection against exposure to the following:
 - a. Equipment;
 - b. Strong oxidizing chemicals, acids, or bases;
 - c. Flames, including welding sparks;
 - d. Temperatures in excess of 160 deg. F;
 - e. Dust
 - f. Ultraviolet radiation (i.e. sunlight); and
 - g. Inclement weather.
- 3. Whenever possible, provide a 6-inch minimum air space between rolls.
- 4. Containers/rolls shall not be stacked.

C. On-Site Handling:

 Handle rolls per Geomembrane Manufacturer's recommendations and as necessary to prevent damage.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. High Density Polyethylene (HDPE) White Textured Geomembrane.
 - HDPE geomembrane shall be white, textured, 60-mil product approved by the Engineer and/or Geosynthetic Quality Assurance Consultant.
 - 2. The Contractor shall submit, with the bid, written certification from the proposed Geomembrane Manufacturer that geomembrane products proposed in the bid satisfy the following requirements:
 - a. The proposed HDPE compound shall be comprised entirely of virgin materials. Compliance with this specification shall be documented in accordance with Geomembrane Manufacturer's quality control program and submitted to the Geosynthetic Quality Assurance Consultant with the written conformance certification.

1965 Section 02600 HDPE Geomembrane

- b. The proposed Geomembrane Manufacturer shall certify that any plasticizers, fillers and additives incorporated into the manufacturing process for the proposed HDPE geomembrane have demonstrated acceptable performance on past projects.
- The proposed geomembrane shall meet the requirements of Geosynthetic Research Institute's test method GM 13.
- The nominal thickness of proposed geomembrane shall be 60 mil., or as approved by the Engineer and/or Geosynthetic Quality Assurance Consultant.
- Geomembrane sheets shall be visually consistent in appearance and shall contain
 no holes, blisters, undisbursed raw materials or other signs of contamination by
 foreign material. Geomembrane must have no striations, roughness or bubbles
 on the surface.

B. Seaming Apparatus

- Thermal fusion welding machines used for joining geomembrane surfaces may
 be either extrusion or hot wedge. These machines shall include sufficient
 temperature and rate-of-travel monitoring devices to allow continuous
 monitoring of operating conditions.
- One spare, operable thermal fusion seaming device shall be maintained on site at all times.

C. Field Test Equipment

- 1. Field Tensiometer: the field tensiometer shall be calibrated within three months prior to project start date over the range of field test values.
- 2. Air Channel Test Equipment: air channel test equipment shall consist of hoses, fittings, valves and pressure gauge(s) needed to deliver and monitor the pressure of compressed air through an approved pressure feed device.
- 3. Air Compressor: the air compressor utilized for field testing shall be capable of producing and maintaining an operating pressure of at least 50 psi.
- Vacuum Box: the vacuum box shall consist of a vacuum gage, valve, and a
 gasket around the edge of the open bottom needed to apply vacuum to a surface.

2.02. CONFORMANCE TESTING REQUIREMENTS

A. Geomembrane shipped to site shall undergo conformance testing. Manufacturer's roll certificates may be used for conformance evaluation at the option of the Geosynthetic Assurance Consultant. Nonconforming material shall either be retested at the direction of the Geosynthetic Quality Assurance Consultant or removed from site and replaced at Contractor's expense.

1965 Section 02600 HDPE Geomembrane

NOT FOR CONSTRUCTION

B. Conformance Test Methods

- Samples will be located and collected by the Geosynthetic Quality Assurance
 Consultant at a rate of one sample per 100,000 square feet of geomembrane
 delivered to site.
- One sample will be obtained from each geomembrane production batch delivered to the site.
- 3 Samples shall be cut by Geomembrane Installer and be at least 45 square feet in size.
- 4. Samples shall be tested in accordance with Table 1 (Smooth) or Table 2 (Textured) specified in GRI Test Method GM13.
- Geomembrane thickness shall be measured a minimum of three times per panel during deployment to verify conformance with GRI Test Method GM13.

C. Role of Testing Laboratories

- The Geosynthetic Quality Assurance Consultant will be responsible for acquiring samples of the geomembrane for conformance testing. The Owner or Geosynthetic Quality Assurance Consultant will retain an independent, third party laboratory to perform conformance testing on samples of geomembrane.
- Retesting of geomembrane panels by the Geomembrane Installer because of
 failure to meet any of the conformance specifications can only be authorized by
 the Geosynthetic Quality Assurance Consultant. Non-conforming panels may be
 retested in accordance with Subsection 2.02(B) and 2.02(D) under authorization
 of the Geosynthetic Quality Assurance Consultant only.
- The Geomembrane Manufacturer and/or Geomembrane Installer may perform independent tests in accordance with methods and procedures specified in Subsection 2.02(B). Results shall not be substituted for quality assurance testing described herein.

D. Procedures for Determining Conformance Test Failures

If conformance test results fail to meet specifications, the roll and/or batch may be retested using specimens from either the original roll sample or from another sample collected by the Geosynthetic Quality Assurance Consultant. Two additional tests (retests) shall be performed for each failed test procedure. Each retest shall consist of multiple specimen tests if multiple specimens are specified in the test procedure. If the results of both retests meet specifications, the roll and batch will be considered to have passed conformance testing.

1965 Section 02600 HDPE Geomembrane

- 2. Failure of any retest shall be cause for rejection of the entire roll or batch depending on the type of failing test. The Geosynthetic Quality Assurance Consultant reserves the right to collect samples from other rolls of a particular batch for further conformance testing. The Geosynthetic Quality Assurance Consultant may choose to accept only a portion of the batch on the basis of the results of conformance testing of samples collected from other rolls.
- 3. If retesting does not result in conformance with the specifications as defined in preceding paragraph, or if there are any other nonconformities with the material specifications, the Contractor shall remove the rolls from use in the project. The Contractor shall also be responsible for removal of rejected geomembrane from the site and replacement with acceptable geomembrane at no additional cost to the Owner.

PART 3 - EXECUTION

3.01 PRE-CONSTRUCTION MEETING

- A. A Pre-Construction Meeting shall be held at the site to discuss and plan the details of geomembrane installation. This meeting shall be attended by the Geomembrane Installer, Owner, Engineer and the Contractor.
- B. The following topics relating to geomembrane installation shall be addressed:
 - 1. Responsibilities of each party.
 - 2. Lines of authority and communication.
 - 3. Methods for documenting, reporting and distributing documents and reports.
 - 4. Procedures for packaging and storing archive samples.
 - Review of the schedule for all installation and quality assurance testing, including third-party testing turnaround times.
 - 6. Review of panel layout, access and numbering systems for panels and seams including details for marking on the HDPE geomembrane.
 - Procedures and responsibilities for preparation and submittal of as-built drawings.
 - Temperature and weather limitations, installation procedures for adverse weather conditions and defining acceptable subgrade or ambient moisture and temperature conditions for working during liner installation.
 - 9. Subgrade conditions, dewatering responsibilities and subgrade maintenance plan.
 - 10. Deployment techniques including allowable subgrade for geomembrane.
 - 11. Procedures for covering of the geomembrane to prevent damage.

1965 Section 02600 HDPE Geomembrane

NOT FOR CONSTRUCTION

- 12. Plan for minimizing wrinkles in the geomembrane.
- 13. Measurement and payment schedules.
- 14. Site health and safety procedures/protocols.

3.02 SUBGRADE PREPARATION

- A. Contractor shall prepare a subgrade surface in accordance with Section 02300, Earthwork.
- B. The Contractor shall not excavate more than the amount of anchor trench required for one day of geosynthetics deployment, unless otherwise specified by the Geosynthetic Quality Assurance Consultant. Rounded corners shall be provided in the trenches where the geosynthetics enter the trench to allow them to be uniformly supported by the subgrade and to avoid sharp bends. The geosynthetics shall not be supported by loose soils in anchor trenches.
- C. The Geomembrane Installer shall visually inspect the subgrade immediately prior to geomembrane deployment. Inspection shall verify that there are no potentially harmful foreign objects present, such as sharp rocks and other deleterious debris. Any foreign objects encountered shall be removed by Geomembrane Installer or Contractor. All subgrade damaged by construction equipment and deemed unsuitable for geomembrane deployment shall be repaired prior to geomembrane deployment. All repairs shall be approved by the Geosynthetic Quality Assurance Consultant and Geomembrane Installer. The responsibility for preparation, repairs, and maintenance of the subgrade shall be defined in the preconstruction meeting. The Geomembrane Installer shall provide the Geosynthetic Quality Assurance Consultant with written acceptance of subgrade surface over which geomembrane is deployed (Part 1.05C) for each day of deployment.

3.03 GEOMEMBRANE DEPLOYMENT

- A. Geomembrane shall not be deployed until all applicable certifications/quality control certificates listed in Subsection 1.05 of this section and conformance testing listed in Subsection 2.02 of this section are submitted and approved by the Geosynthetic Quality Assurance Consultant. Any geomembrane deployed prior to approval by the Geosynthetic Quality Assurance Consultant shall be at the sole risk of the Geomembrane Installer and/or Contractor. If material installed prior to approval by the Geosynthetic Quality Assurance Consultant does not meet the requirements of this specification, it shall be removed from the site at no additional cost to the Owner.
- B. Geomembrane will be deployed according to submitted panel layout drawing as approved by the Geosynthetic Quality Assurance Consultant. The Geosynthetic Quality Assurance Consultant is to be notified of and approve any revisions or modifications to the approved panel layout drawing prior to deploying geomembrane in the area of review.
- C. Adequate temporary anchoring (sand bags, tires, etc.) that will not damage the geomembrane shall be placed on a deployed panel to prevent uplift by wind.
- D. Geomembrane shall not be deployed if:

1965 Section 02600 HDPE Geomembrane

- 1. Ambient temperatures are below 41 degrees F (5 degrees C) or above 104 degrees F (40 degrees C) measured six inches above geomembrane surface unless approved by the Geosynthetic Quality Assurance Consultant.
- 2. Precipitation is expected or in the presence of excessive moisture or ponded water on the subgrade surface.
- 3. Winds are excessive as determined by Geomembrane Installer in agreement with the Geosynthetic Quality Assurance Consultant.
- 4. The Geosynthetic Quality Assurance Consultant will have the authority to suspend work during such conditions.
- E. The Geomembrane Installer shall be responsible for conformance with the following requirements:
 - Equipment utilized for installation/quality assurance testing does not damage geomembrane. Such equipment shall have rubber tires and a ground pressure not exceeding 5 psi or total weight exceeding 750 lbs. Only equipment necessary for installation and quality assurance testing is allowed on the deployed geomembrane.
 - 2. Personnel working on geomembrane do not damage geomembrane (activities such as smoking or wearing damaging clothing shall not be allowed).
 - 3. Method of deployment does not damage geomembrane.
 - 4. Method of deployment minimizes wrinkles.
 - 5. Temporary loading or anchoring does not damage geomembrane.
 - 6. Direct contact with geomembrane is minimized.
- F. No vehicles shall be allowed on deployed geomembrane under any circumstances.

3.04 FIELD SEAMS

- A. Seam Layout
 - In general, seams shall be oriented parallel to the line of the maximum slope. In corners and at other odd-shaped geometric intersections, number of seams should be minimized. If at all possible, seams shall not be located at low points in the subgrade unless geometry requires seaming to be done at these locations.
 - 2. A seam numbering system compatible with the panel numbering system shall be agreed upon at the Pre-Construction Meeting.

NOT FOR CONSTRUCTION

1965 Section 02600 HDPE Geomembrane

C. Field Test Methods

- 1. Ten 1-inch-wide samples described above under Part 3.06(B)(3) shall be field tested for peel (5 samples) and shear (5 samples) in accordance with GRI GM 19.
- One seam sample shall be field tested for peel and shear at the end of each continuous field seam 100 feet or greater in length.
- Testing shall be performed in accordance with ASTM D6392 using a field tensiometer or equivalent device to qualitatively and quantitatively determine mode of failure.
- 4. Seam shall be considered passing if failure in both peel and shear meet criteria listed in GRI GM 19.
- The procedures specified in Subsection 3.06(D) shall be implemented when sample passes field tensiometer test.

D. Laboratory Test Methods

- Laboratory testing of seam samples shall be conducted by the Geosynthetic Quality Assurance Laboratory under contract with the Geosynthetic Quality Assurance Consultant or Owner. Five specimens shall be tested in shear and five in peel.
- Laboratory testing shall be conducted in accordance with GRI GM 19.
- 3. For both seam shear and peel tension tests, an indication will be given for each specimen tested which defines locus of failure.
- 4. For shear tests, the following values, along with the mean and standard deviation where appropriate, will be reported for each specimen tested:
 - a. Maximum tension in pounds per square inch.
 - b. Elongation at break (up to a tested maximum of 100 percent).
 - c. Locus of failure using ASTM D6392 designations.
- 5. For peel tests, the following values, along with the mean and standard deviation where appropriate, will be reported for each specimen tested:
 - a. Maximum tension in pounds per square inch.
 - b. Seam separation (expressed as percent of original seam area).

1965 Section 02600 HDPE Geomembrane

NOT FOR CONSTRUCTION

- c. Locus of failure.
- Retesting of seams due to nonconformance with specifications may be performed at the discretion of the Geosynthetic Quality Assurance Consultant.

E. Destructive Seam Test Failure

- Shear and peel test results derived from testing described in Parts 3.06(C) and
 3.06(D) shall comply with GRI GM 19 for seam to be considered acceptable.
- 2. The Geomembrane Installer has two options in determining the repair boundary whenever a seam has failed destructive testing:
 - a. The seam can be reconstructed between the two previously tested and passed destructive sample locations; or,
 - The Geomembrane Installer can trace the welding path to an intermediate b. location at least ten feet from point of failed test in each direction and obtain destructive test samples collected from these locations. If destructive tests on these samples are acceptable, then the seam shall be reconstructed between the intermediate locations. If either sample fails, the process may be repeated until an acceptable seam test has been performed on both sides of the original failed sample. If a passing sample is not realized on one (or both) side of the original failed sample, then seam repair must extend to the end(s) of the seam. Retesting of seams according to this procedure shall utilize the sampling methodology described in Part 3.06(B). The Owner reserves the right to terminate this process, at the discretion of the Geosynthetic Quality Assurance Consultant, after the second retesting. An additional sample taken from the reconstructed zone must pass destructive seam testing if destructive sample failure(s) causes reconstruction.
- The Geosynthetic Quality Assurance Consultant shall be responsible for documenting all actions taken in repairing seams. The Geomembrane Installer will be responsible for keeping the Geosynthetic Quality Assurance Consultant informed of seaming progress.
- Additional fees for destructive seam test failures shall be assessed to the Contractor and deducted from payment. This fee shall be assessed only if the failing sample is a laboratory sample.

3.07 ELECTRONIC LEAK LOCATION SURVEY

- A. The Owner shall have the option to conduct an electronic leak location survey. Leak location survey shall be performed by the Leak Location Contractor under the observation of the Geosynthetic Quality Assurance Consultant.
- Leak Location Contractor shall identify actions required by Contractor to prepare the site for the leak location survey.
- C. Contractor shall ensure that the layers above and below the geomembrane contains sufficient moisture to conduct a leak location survey. Typically, a moisture content of earth materials of 1% to 2% by weight is sufficient to conduct the survey. If the moisture content of layers above and/or below the geomembrane is not sufficient per the requirements of the Leak Location Contractor, Contractor shall add moisture to the layers, as required.
- D. Contractor shall provide electrical isolation of the metal marker posts, batten bars, and concrete structures, as requested by Leak Location Contractor.
- E. Leak Location Contractor shall inspect the site prior to commencing the survey to ensure all site preparations are completed and the site conditions are appropriate for conducting the leak location survey.
- F. Any discrepancy in the required site preparation detailed in the Leak Location Contractor's Work Plan or site conditions shall be reported to the Contractor for corrective or appropriate action.
- G. After the final layer is placed above the geomembrane, conduct a leak location survey on the final layer material using the procedures for surveys with earth materials covering the Geomembrane as described in ASTM D 7007.
- H. A leak detection sensitivity test using an artificial leak shall be conducted on the geomembrane for each set of equipment used before the equipment is used on for the leak location survey, as described in ASTM D 7007 to determine the detection distance for the survey.
- The leak location survey shall be taken on survey lines or on a grid spaced no farther apart than twice the leak detection distance as determined in the leak detection sensitivity test.
- J. The Leak Location Contractor shall inform the Owner and/or Engineer and mark the locations of all identified or indicated leaks with a flag or spray paint. The Geomembrane Installer shall repair the defect/hole as detailed in Part 3.08 of this Section.

3.08 DEFECTS AND REPAIRS

A. The geomembrane shall be examined by the Geomembrane Installer and the Engineer for defects, holes, blisters, undispersed raw materials, and any signs of contamination by foreign matter. The geomembrane surface shall be swept and/or washed by the Geomembrane Installer if the amount of dust or mud inhibits examination. The

1965 Section 02600 HDPE Geomembrane

NOT FOR CONSTRUCTION

Contractor shall provide a water truck, an operator, clean water and hoses as reasonably necessary to assist the Geomembrane Installer in this activity.

- B. Portions of geomembrane exhibiting flaws, or failing a non-destructive or destructive (if conducted) test, shall be repaired or replaced by the Geomembrane Installer. Repair procedures available include:
 - 1. Patching used to repair large holes, tears, undispersed raw materials, contamination by foreign matter, holes resulting from destructive sampling (if conducted), and locations where seam overlap is insufficient;
 - 2. Capping used to repair large lengths of failed seams; and
 - 3. Additional Procedures used upon recommendation of the Geomembrane Installer if agreed to by the Engineer.
- C. Patches or caps.
 - 1. Extend patch or cap 6 inches (minimum) beyond the edge of the defect.
 - 2. Round corners of patch and/or cap (suggest 3-inch radius).
 - 3. Repair procedures, equipment, materials, and techniques will be approved by the Geosynthetic Quality Assurance Consultant prior to repair.
 - 4. Geomembrane below large caps shall be appropriately cut to avoid water or gas collection between two sheets.
- D. The Geomembrane Installer shall mark on the geomembrane (using a non-puncturing writing utensil), repair date, time, and personnel involved.
- E. Each repair shall be non-destructively tested in accordance with Part 3.05. Large caps may require destructive test sampling in accordance with Part 3.06 at the discretion of the Geosynthetic Quality Assurance Consultant.
- F. Repairs which fail testing shall be redone and retested until a passing result is obtained. The Geomembrane Installer will perform non-destructive testing on repairs and will document retesting of repairs.
- G. The Geosynthetic Quality Assurance Consultant will document repairs, repair testing, and retesting results.
- H. The Geomembrane Installer shall cut and seam wrinkles which may adversely affect long-term integrity of the geomembrane, hinder subsequent construction of overlying layers, or impede drainage off of the geomembrane after it is covered by soil. Seaming shall be done in accordance with procedures described in Parts 3.04(B) and 3.04(C), and it shall be subject to test provisions of Parts 3.05 (non-destructive testing) and 3.06 (destructive testing if conducted).

1965 Section 02600 HDPE Geomembrane

3.09 PROTRUSIONS AND CONNECTIONS TO GEOMEMBRANE

- A. If required, the Geomembrane Installer shall install geomembrane around utility poles, guy wires, and other structures according to the Contract Drawings and the following requirements:
 - 1. Use minimum 1-ft long geomembrane pipe boots and steel clamps to scal the geomembrane around pole or structure.
 - 2. Use standard welding procedures to seam the geomembrane boot to the geomembrane.
 - Seaming performed on and around penetrations, and other appurtenances shall be non-destructively tested using the vacuum testing method.

3.10 SURVEY DOCUMENTATION

A. The Geomembrane Installer shall survey the completed geomembrane prior to covering and provide the Geosynthetic Quality Assurance Consultant with 24-hour notification of survey. The Contractor shall document the location of all seams (panel corners acceptable), destructive test samples (if conducted) and repairs. The Contractor shall provide survey data to the Geosynthetic Quality Assurance Consultant within two working day of survey completion.

3.11 DAILY FIELD INSTALLATION REPORTS

- A. At the beginning of each day, the Geomembrane Installer shall provide the Geosynthetic Quality Assurance Consultant with a report for all work completed the previous day.
- B. The Daily Field Installation Report shall include the following:
 - 1. The total amount and location of geomembrane placed,
 - The total length and location of seams completed, technician name and welding unit numbers.
 - A drawing or sketch depicting the geomembrane installed the previous day including the panel number, seam number and locations of non-destructive and destructive testing (if conducted).
 - 4. Results of pre-qualification test seams, if available.
 - Results of non-destructive testing.
- C. Destructive test results (if conducted) shall be reported within 48 hours or prior to covering the geomembrane, whichever is practical.

1965 Section 02600 HDPE Geomembrane

3.12 MATERIAL ABOVE GEOMEMBRANE

- A. The Geosynthetic Quality Assurance Consultant and Geomembrane Installer shall verify the area of geomembrane completion prior to placement of material over the geomembrane.
- B. Soils Apply following general criteria for covering of the geomembrane:
 - Do not place soils on the geomembrane at an ambient temperature below 32 degrees F, (0 degrees C) nor above 104 degrees F (40 degrees C), unless otherwise specified.
 - 2. Do not drive equipment used for placing soil directly on the geomembrane.
 - A minimum thickness of 1 foot of soil is specified between a low ground pressure dozer (maximum contact pressure of 5 lb/sq. inch) and the geomembrane.
 - 4. A minimum thickness of 2 feet of soil is required between rubber-tired vehicles and the geomembrane.
 - 5. Do not compact soils placed directly on geomembrane.
 - 6. Damage to the geomembrane resulting from placement of cover soils shall be repaired in accordance with Part 3.08 by the Geomembrane Installer at the Contractor's expense.
 - 7. Do not push soil downslope. Soil shall be placed over the geomembrane starting from base of the slope, up to top of the slope.


END OF SECTION


1965 Section 02600 HDPE Geomembrane

NOT FOR CONSTRUCTION

勇

SHEETS





+

